

---

*Neutral Wind Meter (NWM)*  
*and*  
*Ion Velocity Meter (IVM)*

---

**Coupled Ion-Neutral Dynamics Investigation  
(CINDI)  
Confirmation Review for NASA**

August 29, 2001  
UTD

---


---

8:15 - 8:20	Welcome, Introductions	Rod Heelis
8:20 - 8:25	Review Board Purpose and Scope	Bill Gibson
8:25 - 8:40	Science Overview	Rod Heelis
8:40 - 8:50	Project Management - Organization	Ron Lippincott
8:50 - 9:10	Project Management - Schedule	Ron Lippincott
9:10 - 9:25	Project Management - Risk Management	Ron Lippincott
9:25 - 9:35	Project Management - Review Process	Ron Lippincott
9:35 - 9:55	Systems Engineering	Ben Holt
9:55 - 10:05	Verification	Ben Holt
10:05 - 10:25	Performance Assurance	Larry Harmon
10:25 - 10:40	Break	
10:40 - 10:55	Instrument Overview	Ben Holt
10:55 - 11:10	Integration and Test	Ben Holt
11:10 - 11:15	Spacecraft Integration Support	Ben Holt
11:15 - 11:25	Flight Operations	Rod Heelis
11:25 - 11:35	Data Analysis	Rod Heelis
11:35 - 12:05	Project Management - Cost	Ron Lippincott
12:05 - 12:35	Summary Review and Action Item Discussion	Bill Gibson
12:35 - 1:30	Lunch	
1:30 - As Required	Caucus of Review Team	Bill Gibson

---

---


# SCIENCE OVERVIEW




**In-situ plasma density measurements show a broad spectrum of horizontal scales and a broad spectrum of depletion magnitudes.**

# EFFECTS OF PLASMA STRUCTURE ON RADIO COMMUNICATIONS

---



**High Frequency radio waves are reflected and refracted from the ionosphere.  
Uncertainties in the propagation path lead to object location errors.**



**Navigation and communication beacons radiate signals that become distorted by ionospheric structure.  
Distortions lead to signal loss due to phase and amplitude variations.**

## Top Level Questions

**What is responsible for the variations ?**

**Can they be understood well enough to predict ?**

## Major Considerations


### Climatology


- **Seasonal/longitude variations in electric fields.**
- **Seasonal/longitude variations in seed perturbations.**

### Weather

- **Daily variations in electric fields.**
- **Daily variations in neutral winds.**
- **Daily variations in seed perturbations.**


- Enhanced vertical  $E \times B$  dynamo drifts and bubble plasma drifts are produced by F-region polarization fields.
- Large Scale Polarization Fields map along the magnetic field and may be shorted-out through a conducting E-region.
- F-region fields most effective when E-region is in darkness at both ends of magnetic field.





## SUMMER

Magnetic Meridian with Positive Declination  
Aligned with Sunset Terminator



## WINTER

Magnetic Meridian with Negative Declination  
Aligned with Sunset Terminator



- **Variations in the seed perturbations**  
Gravity **waves** from weather systems
- **Variations in the height of the F-peak**  
Local-time history of the vertical **ExB drift**  
Magnitude and persistence of the post-sunset enhancement.  
**Neutral winds.**
- **Variations in the flux-tube integrated conductivity**  
**Neutral wind** induced field-aligned plasma motions.  
**ExB drift** history

- **What are the relationships between the behavior of F-region neutral winds and the daily variability of ExB drifts ?**
- **How do F-region neutral winds and ExB drifts influence the evolution of irregularities ?**

---

## Ion Density and Drift Velocity

Retarding Potential Analyzer (RPA)

to measure kinetic energy of ions along the sensor look direction.

Ion Drift Meter (IDM)

to measure ion arrival angle with respect to sensor look direction.

RPA and IDM measure incoming ion flux and thus ion density.

## Neutral Wind Velocity

Ram Wind Sensor (RWS)

to measure kinetic energy of neutrals along the sensor look direction.

Cross-Track Wind Sensor (CTS)

to measure neutral arrival angle with respect to sensor look direction

---

## IDM

**Horizontal / Vertical fixed or alternates every 1/8 or 4 secs**

**Difference Amplifier Output Sampled at 128 Hz**

**16 bit samples**

**4 Log Amp Outputs Sampled sequentially at 16 Hz**

**16 bit samples**

## RPA

**Retarding Grid Voltage Stepped at 32 Hz**

**Sweep Sequence Selected from Memory; One of 8 Blocks with 32 Locations**

**32 Steps can comprise 1 sweep ; 2 sweeps ; 4 sweeps**

**Electrometer Output Sampled at 32 Hz**

**16 bit samples**

**Total Telemetry Rate 3072 bps including housekeeping and packetization**

---

**CTS**

**Horizontal and Vertical arrival angles measured separately with  
2 Difference Amplifier Output each Sampled at 16 Hz**

**16 bit samples**

**4 Log Amp Outputs Sampled sequentially at 16 Hz**

**16 bit samples**

**RWS**

**Retarding Grid Voltage Stepped at 32 Hz**

**Sweep Sequence Selected from Memory; One of 8 Blocks with 32 Locations**

**32 Steps can comprise 1 sweep ; 2 sweeps ; 4 sweeps**

**Electrometer Output Sampled at 32 Hz**

**16 bit samples**

**Total Telemetry Rate 1536 bps including housekeeping and packetization**

---

**Minimum Success Criteria**

**Science**

**Describe the local time dependence of the zonal wind at the equator  
What are storm influences ?**

**Operations**

**Quality Data from NWM below 450 km for ~40 day period  
Ascending node rotates 24 hours in local time  
Line of Apsides rotates at least 360°**

**Mission**

**Data integrated into CINDI data system and delivered to NSSDC**

---

## Comprehensive Success Criteria

### Science

**Describe the local time and seasonal dependencies in zonal and meridional neutral wind at the equator.**

**Describe the local time and seasonal dependencies in zonal and meridional ion drift at the equator.**

**How does the appearance of plasma structure affect the ion and neutral motions ?**

### Operations

**Quality Data from NWM and IVM below 450 km for ~270 day period**

**Ascending node rotates 24 hours in local time at solstices and equinox**

**Line of Apsides rotates at least 360°**

### Mission

**Data integrated into CINDI data system and delivered to NSSDC**

---

## Inputs Level 1 Document Complete

### Contents

#### **Science Definition**

- Baseline Science Objectives
- Instruments

#### **Mission Definition**

- Organizations Involved

#### **Programmatic Requirements**

- Science and Mission Success
- Ground System
- Data Management

#### **Cost Management and Scope Reduction**

- Options and Impacts

### Status

**Delivered to NASA Headquarters and Explorer Office**



---

Principal Investigator - R.A. Heelis

Overall Direction of Investigation

IVM and NWM Requirements

Data Analysis and Distribution System

Science and Technical Goals and Priorities

Co-Investigator - G.D. Earle

NWM Instrument Design Features

NWM Instrument Evaluation and Test

Data Analysis and Interpretation


Co-Investigator - P.H. Mahaffy

NWM optics design

NWM ion source and detector performance

Data Analysis and Interpretation

# **PROJECT MANAGEMENT - ORGANIZATION**



---

## Principal Investigator (PI)

- Responsible for successful performance of CINDI investigation throughout all phases and facets of project
  - Science Objectives
  - Instrumentation
  - Science Operations
  - Mission Planning Support
  - Data Analysis and Publication
  - Schedule and Cost
  - E/PO
- Ultimate decision making authority on allocation of resources in dispute
- Point of Contact for science matters
- Final decision maker on descope based on recommendations of PM and SE and approval of NASA and C/NOFS Project offices

---

### Project Manager (PM)

- By delegation from the PI, PM is responsible for Implementation Phases of the project
- Manage day to day activities of the project
- Directly responsible for cost and schedule development and tracking
- Responsible for cost and schedule reserves with concurrence of PI
- Point of Contact for all management matters
- Responsible for implementation, control and tracking of risk management

---

## System Engineer (SE)

- Responsible for overall instrument technical design
- Responsible for identification and control of all interfaces
- Allocation and tracking of mass, power and telemetry resources
- Lead technical team member in development, manufacture, test, integration and field support of instruments
- Responsible for Instrument Requirements Document
- Responsible for linkage between science objectives, instrument specifications, subsystem specification and instrument verification

---

### Product Assurance Manager (PA)

- Responsible for product assurance performance consistent with C/NOFS project requirements and SMEX Safety, Reliability and Quality Assurance Requirements document and ISO 9000
- Implementation of CINDI Project Safety Plan requirements
- Responsible for CINDI Safety inputs to C/NOFS Project Safety Plan
- Reports to CINDI PM
  - Successful UTD approach used on past projects
  - PA regularly meets with PI and all CINDI engineers
  - Open communication with key CINDI personnel including PI
  - No traditional separate PA department

- 
- Technical decisions based on meeting science objectives with minimum risk and minimum resource usage
  - Non-technical decisions based on minimizing schedule and cost risks while solving technical problems with judicious use of resources
  - Technical decisions that do not affect interfaces, performance or resources concerning subsystems will be made by subsystem engineer
  - Decisions that involve interface between subsystems and do not affect cost, schedule or performance will be made by SE
  - Decisions that affect spacecraft interface will be made by consensus of SE and PM with PI informed
  - Decisions to change technical resource allocations will be made by SE with PM and PI informed
  - Decisions that affect instrument performance or science return will be made by the PI
  - Decisions that affect schedule or cost are made by the PM with recommendations by SE - Release of cost or schedule reserves is by consensus with PI
  - Decisions on descope will be made by PI with recommendations by PM & SE and approval by C/NOFS & NASA project offices
-



- 
- Preliminary negotiations complete on NASA/UTD Phase B/C/D/E contract
  - SOW and Deliverables negotiated and completed
  - NASA legal office performing last review
  - UTD operating on Pre-award provision of Phase B/C/D/E contract
  - Goal of Contract signed by both parties by 1 Sept 01

## CONTACT INFORMATION

---

Name	Organization	Phone Number	Email Address
R.A. Heelis (Rod)	UTD	(972) 883-2822	heelis@utdallas.edu
G.D. Earle (Greg)	UTD	(972) 883-6828	earle@utdallas.edu
C.R. Lippincott (Ron)	UTD	(972) 883-2819	lippinco@utdallas.edu
B.J. Holt (Ben)	UTD	(972) 883-2821	holt1@airmail.net
L.L. Harmon (Larry)	UTD	(972) 883-2823	harmon@utdallas.edu
Joseph Bolek	NASA/GSFC	(301) 286-1390	joseph.t.bolek@gsfc.nasa.gov
Jim Byrd	NASA/GSFC	(301) 286-7622	jim.byrd@gsfc.nasa.gov
Bill Davis	NASA/GSFC	(301) 286-3038	bdavis@pop400.gsfc.nasa.gov
Robert Davis	Aerospace/AFRL	(505) 872-6235	robert.j.davis@aero.org
Bronek Dichter	AFRL	(781) 377-3991	bronek.dichter@hanscom.af.mil
Laila Jeong	AFRL	(781) 377-3671	laila.jeong@hanscom.af.mil

**Mailing Address:**

The University of Texas at Dallas  
FO22  
POB 830688  
Richardson, TX 75083-0688

**Physical Address:**

The University of Texas at Dallas  
2601 N. Floyd Road  
Richardson, TX 75080  
**FAX:** (972) 883-2761


# **PROJECT MANAGEMENT - SCHEDULE**

- 
- Schedule developed and tracked in SureTrak by Primavera
  - Developed from bottom with subsystem engineers and SE
  - Generate task lists for each subsystem and contract requirements & deliverables
  - WBS defined and formatted
  - Identify task relational dependencies and durations
  - Align to milestone constraints for major reviews, project requirements, and deliverables
  - Add resources to tasks
  - Level resources

- 
- Master schedule kept on CSS server
  - Master schedule available to all disciplines as read only
  - Subsystem engineers (SSE) also have discipline schedules distilled from master schedule
  - SSEs report weekly on status
  - Each SSE indicates work accomplished on discrete schedule task activity
  - Status updates entered by PM office
  - Changes or adjustments to schedule negotiated by PM and SE and/or SSE

- 
- Total float for critical path to instrument delivery is tracked
  - Keep critical path total float non-negative
  - Identify and evaluate loss of float on non-critical path items
  - Informal status reporting between monthly reports by telephone, fax, and e-mail
  - Written status report monthly
  - Approach enables us to manage early schedule to maintain schedule margin
  - Able to spot problems early to apply solutions

- 
- Have 22+ days float in critical path to delivery of each instrument
  - Critical path
    - Last PWA in board series, then with its parts del, fab, assy and test
      - For IVM = Digital Controller Board (IVM-3)
      - For NWM = Digital Controller Board (EBOX-3)
    - Then series sensor/instrument assy & test, pack and ship
  - Recent trends indicate no slippage
  - Currently performing resource leveling









Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001												2002																	
						JUL	AUG			SEP			OCT			NOV			DEC			JAN			FEB			MAR							
						20	30	06	13	20	27	03	10	17	24	01	08	15	22	29	05	12	19	26	03	10	17	24	31	07	14	21	28	04	11
CNNW2098	RWS-4 REP/DEF PS PWA Schematic	0	26 JUN 01	26 JUN 01		RWS-4 REP/DEF PS PWA Schematic																													
CNNW2100	RWS-4 REP/DEF PS PWA Layout	90 *	26 JUN 01	11 DEC 01	59d	RWS-4 REP/DEF PS PWA Layout																													
CNNW2106	RWS-4 REP/DEF PS PWA PL	1	26 JUN 01	03 AUG 01	160d	RWS-4 REP/DEF PS PWA PL																													
CNNW1475	RWS-4 REP/DEF PS PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	158d	RWS-4 REP/DEF PS PWA Verif Test Proc																													
CNNW2102	RWS-4 REP/DEF PS PWB Drill Drawing	2	12 DEC 01	13 DEC 01	59d	RWS-4 REP/DEF PS PWB Drill Drawing																													
CNNW2104	RWS-4 REP/DEF PS PWA Assy Drwg	5	14 DEC 01	20 DEC 01	66d	RWS-4 REP/DEF PS PWA Assy Drwg																													
CNNW2108	Procure RWS-4 REP/DEF PS PWB	10	14 DEC 01	07 JAN 02	59d	Procure RWS-4 REP/DEF PS PWB																													
CNNW2112	RWS-4 REP/DEF PS PWA Kitting & Traveler Prep	2	08 JAN 02	09 JAN 02	59d	RWS-4 REP/DEF PS PWA Kitting & Traveler Prep																													
CNNW2114	RWS-4 REP/DEF PS PWA Assembly	3	10 JAN 02	14 JAN 02	59d	RWS-4 REP/DEF PS PWA Assembly																													
CNNW2116	RWS-4 REP/DEF PS PWA Initial C/O Tuning	2	15 JAN 02	16 JAN 02	59d	RWS-4 REP/DEF PS PWA Initial C/O Tuning																													
CNNW2118	RWS-4 REP/DEF PS PWA Stand-Alone Verify	5	17 JAN 02	23 JAN 02	59d	RWS-4 REP/DEF PS PWA Stand-Alone Verify																													
RWS Sensor Assembly & Test																																			
		117	03 AUG 01	28 JAN 02	58d	RWS Sensor Assembly & Test																													
CNNWP005	Stack & Wire Proto RWS PWA's	3	03 AUG 01	07 AUG 01	14d	Stack & Wire Proto RWS PWA's																													
CNNWP008	Proto RWS Vacuum Testing	4	08 AUG 01	13 AUG 01	14d	Proto RWS Vacuum Testing																													
CNNWP011	Proto RWS Test Effort Complete	0		13 AUG 01	14d	Proto RWS Test Effort Complete																													
CNNW2170	Temporary RWS Buildup w/PWAs	2	25 JAN 02	28 JAN 02	58d	Temporary RWS Buildup w/PWAs																													
CNNW2191	RWS Sensor Ready for NWM Integration	0		28 JAN 02	58d	RWS Sensor Ready for NWM Integration																													
Cross-Track Wind Sensor (XTRK WS)																																			
		113	14 MAY 01	04 JAN 03	62d	Cross-Track Wind Sensor (XTRK WS)																													
XTRK Detector Subassembly																																			
		90	03 AUG 01	11 DEC 01	80d	XTRK Detector Subassembly																													
CNNW1269	Solenoid Source Control Dwg.	0	03 AUG 01	16 AUG 01		Solenoid Source Control Dwg.																													
CNNW2230	XTRK Filament Procure & Fab	10	03 AUG 01	16 AUG 01	10d	XTRK Filament Procure & Fab																													
CNNW1340	Filament Life Test	20	17 AUG 01	14 SEP 01	10d	Filament Life Test																													
CNNW2212	XTRK Sensor Gauge Assembly (1 of 4)	1	17 AUG 01	17 AUG 01	45d	XTRK Sensor Gauge Assembly (1 of 4)																													
CNNW2215	XTRK Sensor Gauge Assembly (2 of 4)	1	20 AUG 01	20 AUG 01	45d	XTRK Sensor Gauge Assembly (2 of 4)																													
CNNW2218	XTRK Sensor Gauge Assembly (3 of 4)	1	21 AUG 01	21 AUG 01	156d	XTRK Sensor Gauge Assembly (3 of 4)																													
CNNW2221	XTRK Sensor Gauge Assembly (4 of 4)	1	22 AUG 01	22 AUG 01	156d	XTRK Sensor Gauge Assembly (4 of 4)																													
CNNW2227	Assemble XTRK PEV SubAssy	1	19 OCT 01	19 OCT 01	3d	Assemble XTRK PEV SubAssy																													
CNNW1330	XTRK PEV Test (Includes Multiplier/Vibe Test)	25	22 OCT 01	27 NOV 01	3d	XTRK PEV Test (Includes Multiplier/Vibe Test)																													
CNNW2419	Solenoid/PEV Life Test	10	28 NOV 01	11 DEC 01	3d	Solenoid/PEV Life Test																													
Housing & Mechanical Details																																			
		108	01 JUN 01	15 JAN 02	64d	Housing & Mechanical Details																													
CNNW1360	Design Xformer Mtg Parts & Drawings	0 *	01 JUN 01	03 AUG 01		Design Xformer Mtg Parts & Drawings																													
CNNW2204	XTRK Detector Subassy Mech Details Design	34 *	01 JUN 01	20 SEP 01	3d	XTRK Detector Subassy Mech Details Design																													
CNNW2224	Machine/Plate Xformer Mtg Parts	20	06 AUG 01	31 AUG 01	141d	Machine/Plate Xformer Mtg Parts																													
CNNW2260	XTRK Det Details / B/P (x2) & Dome Machining	20	21 SEP 01	18 OCT 01	3d	XTRK Det Details / B/P (x2) & Dome Machining																													



Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001																							
						JUL				AUG					SEP				OCT					NOV					
						20	30	06	13	20	27	03	10	17	24	01	08	15	22	29	05	12	19	26					
CNNW2350	XTRK-3/3Grid PS PWB Drill Drawing	2	19 SEP 01	20 SEP 01	116d																								
CNNW2353	XTRK-3/3Grid PS PWA Assy Drawing	5	21 SEP 01	27 SEP 01	121d																								
CNNW2359	Procure XTRK-3/3Grid PS PWB	10	21 SEP 01	04 OCT 01	116d																								
CNNW2365	XTRK-3/3Grid PS PWA Kitting & Traveler Prep	2	05 OCT 01	08 OCT 01	116d																								
CNNW2368	XTRK-3/3Grid PS PWA Assembly	3	09 OCT 01	11 OCT 01	116d																								
CNNW2371	XTRK-3/3Grid PS PWA Initial Checkout & Tuning	2	12 OCT 01	15 OCT 01	116d																								
CNNW2374	XTRK-3/3Grid PS PWA Stand-Alone Verify	5	16 OCT 01	22 OCT 01	116d																								
XTRK-4 / G1/G3 Filament Regulators PWA																													
		66	26 JUN 01	04 JAN 03	106d																								
CNNW2258	XTRK-4/5 Power Mosfets Procurement	26 *	26 JUN 01	10 SEP 01	139d																								
CNNW2377	XTRK-4/G1/G3 Fil Reg PWA Specification	0	26 JUN 01	04 JAN 03																									
CNNW2380	XTRK-4/G1/G3 Fil Reg PWA Schematic	1	26 JUN 01	03 AUG 01	145d																								
CNNW2383	XTRK-4/G1/G3 Fil Reg PWB Layout	42 *	26 JUN 01	02 OCT 01	106d																								
CNNW2392	XTRK-4/G1/G3 Fil Reg PWA PL	1	26 JUN 01	03 AUG 01	159d																								
CNNW1463	XTRK-4/G1/G3 Fil Reg PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	157d																								
CNNW2386	XTRK-4/G1/G3 Fil Reg PWB Drill Drwg	2	03 OCT 01	04 OCT 01	106d																								
CNNW2389	XTRK-4/G1/G3 Fil Reg PWA Assy Drwg	5	05 OCT 01	11 OCT 01	111d																								
CNNW2395	Procure XTRK-4/G1/G3 Fil Reg PWB	10	05 OCT 01	18 OCT 01	106d																								
CNNW2401	XTRK-4/G1/G3 Fil Reg PWA Kitting & Traveler Prep	2	19 OCT 01	22 OCT 01	106d																								
CNNW2404	XTRK-4/G1/G3 Fil Reg PWA Assembly	3	23 OCT 01	25 OCT 01	106d																								
CNNW2407	XTRK-4/G1/G3 Fil Reg PWA Initial C/O & Tuning	2	26 OCT 01	29 OCT 01	106d																								
CNNW2410	XTRK-4/G1/G3 Fil Reg PWA Stand-Alone Verify	5	30 OCT 01	05 NOV 01	106d																								
XTRK-5 / G2/G4 Filament Regulators PWA																													
		77	26 JUN 01	20 NOV 01	95d																								
CNNW2487	XTRK-5/G2/G4 Fil Reg PWA Schematic	0	26 JUN 01	26 JUN 01																									
CNNW2490	XTRK-5/G2/G4 Fil Reg PWB Layout	52 *	26 JUN 01	16 OCT 01	95d																								
CNNW2499	XTRK-5/G2/G4 Fil Reg PWA PL	1	26 JUN 01	03 AUG 01	158d																								
CNNW1487	XTRK-5/G2/G4 Fil Reg PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	157d																								
CNNW2493	XTRK-5/G2/G4 Fil Reg PWB Drill Drawing	2	17 OCT 01	18 OCT 01	95d																								
CNNW2496	XTRK-5/G2/G4 Fil Reg PWA Assy Drwg	5	19 OCT 01	25 OCT 01	100d																								
CNNW2502	Procure XTRK-5/G2/G4 Fil Reg PWB	10	19 OCT 01	01 NOV 01	95d																								
CNNW2508	XTRK-5/G2/G4 Fil Reg PWA Kitting & Traveler Prep	3	02 NOV 01	06 NOV 01	95d																								
CNNW2511	XTRK-5/G2/G4 Fil Reg PWA Assembly	3	07 NOV 01	09 NOV 01	95d																								
CNNW2514	XTRK-5/G2/G4 Fil Reg PWA Initial C/O & Tuning	2	12 NOV 01	13 NOV 01	95d																								
CNNW2517	XTRK-5/G2/G4 Fil Reg PWA Stand-Alone Verify	5	14 NOV 01	20 NOV 01	95d																								
Transformer Subassembly																													
		21	30 AUG 01	28 SEP 01	122d																								
CNNW1519	Toroids Xformer Design/Fab Drwg	10	30 AUG 01	13 SEP 01	122d																								



Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001												2002											
						J	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	J	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN
CNNW1516	Cup Core Xformer Design/Fab Drwg	10	31 AUG 01	14 SEP 01	123d																								
CNNW1300	WInde Toriod Xformers (x8+4sp)	8	14 SEP 01	25 SEP 01	122d																								
CNNW1306	WInde Cup Core Xformers (x2+2sp)	3	17 SEP 01	19 SEP 01	123d																								
CNNW1309	Stake & Tape Cup Core Xformers	5	20 SEP 01	26 SEP 01	123d																								
CNNW1321	Vacuum Impregnate Toroid Xformers & CCoat	2	26 SEP 01	27 SEP 01	122d																								
CNNW1315	Assemble Xformers into Cup Core	1	27 SEP 01	27 SEP 01	123d																								
CNNW1303	Complete Assy & Inspect of Toroid Xformers	1	28 SEP 01	28 SEP 01	122d																								
XTRK Assembly & Test																													
		113	06 JUL 01	22 JAN 02	62d																								
CNNWP014	Proto XTRK-4 PWA Schematic/Layout	5	06 JUL 01	09 AUG 01	4d																								
CNNWP017	Proto XTRK-4 PWB Procure/Fab	5	10 AUG 01	16 AUG 01	4d																								
CNNWP020	Kit & Assemble Proto XTRK-4 PWA	3	17 AUG 01	21 AUG 01	4d																								
CNNWP023	Assemble Proto XTRK Sensor w/TENRAS Elements	2	22 AUG 01	23 AUG 01	4d																								
CNNWP032	Setup & Perform Vacuum Test on Proto XTRK	3	24 AUG 01	28 AUG 01	4d																								
CNNWP026	Setup & Perform Vibe Test on Proto XTRK	3	29 AUG 01	31 AUG 01	4d																								
CNNWP029	Setup & Perform PEV Life Test on Proto XTRK	5	04 SEP 01	10 SEP 01	4d																								
CNNWP035	Prototype XTRK Testing Complete	0		10 SEP 01	4d																								
CNNW2413	Mount Gauges (x4), PEV to Baseplate	0	16 JAN 02	15 JAN 02	62d																								
CNNW2416	Install Collector Shields to Gauge/Baseplate	1	16 JAN 02	16 JAN 02	62d																								
CNNW2449	Install Dome & Complete Assy	1	17 JAN 02	17 JAN 02	62d																								
CNNW2452	XTRK Detector Subassy Complete	0		17 JAN 02	62d																								
CNNW2455	XTRK Buildup w/PWAs & Temp Solder Connections	3	18 JAN 02	22 JAN 02	62d																								
CNNW2476	XTRK Sensor Ready for NWM Integration	0		22 JAN 02	62d																								
NWM Electronics (EBOX)																													
		169	26 JUN 01	10 APR 02	6d																								
CNNW2251	XTRK PWA's Ready for Next Higher Assy	0		20 NOV 01	95d																								
Enclosure & Misc. Details																													
		46	04 FEB 02	08 APR 02	6d																								
CNNW2690	Design EBox Electronics Enclosure	20	04 FEB 02	01 MAR 02	6d																								
CNNW2687	Machine EBox Pieces (x6) @ Vendor	15	04 MAR 02	22 MAR 02	6d																								
CNNW2681	Plate EBox Pieces (x6) @ Vendor	10	25 MAR 02	05 APR 02	6d																								
CNNW2684	Receive & Inspect EBox Pieces	1	08 APR 02	08 APR 02	6d																								
EBox-1 / LVPS PWA																													
		150	26 JUN 01	14 MAR 02	24d																								
CNNW2504	EBox-1 LVPS PWA Schematic	5	26 JUN 01	09 AUG 01	155d																								
CNNW2507	EBox-1 LVPS PWB Layout	128 *	26 JUN 01	12 FEB 02	24d																								
CNNW1478	EBox-1 LVPS PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	159d																								
CNNW1481	EBox-2 A/D-D/A Conv PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	153d																								

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001						2002					
						J	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN
CNNV2516	EBox-1 LVPS PWA PL	1	10 AUG 01	10 AUG 01	155d												
CNNV2510	EBox-1 LVPS PWB Drill Drawing	2	13 FEB 02	14 FEB 02	24d												
CNNV2513	EBox-1 LVPS PWA Assy Drawing	3	15 FEB 02	19 FEB 02	31d												
CNNV2519	Procure EBox-1 LVPS PWB	10	15 FEB 02	28 FEB 02	24d												
CNNV2068	EBox Board Interconnect Definition	5	20 FEB 02	26 FEB 02	23d												
CNNV2525	EBox-1 LVPS PWA Kitting & Traveler Prep	3	26 FEB 02	28 FEB 02	24d												
CNNV2528	EBox-1 LVPS PWA Assembly	3	01 MAR 02	05 MAR 02	24d												
CNNV2531	EBox-1 LVPS PWA Initial Checkout & Tuning	2	06 MAR 02	07 MAR 02	24d												
CNNV2534	EBox-1 LVPS PWA Stand-Alone Verification	5	08 MAR 02	14 MAR 02	24d												
EBox-2 / A/D & D/A Converter PWA																	
		166	26 JUN 01	05 APR 02	8d												
CNNV2547	EBox-2 A/D-D/A Conv PWA Schematic	1	26 JUN 01	03 AUG 01	135d												
CNNV2557	EBox-2 A/D-D/A Conv PWB Layout	138 *	26 JUN 01	26 FEB 02	8d												
CNNV2587	EBox-2 A/D-D/A Conv PWA PL	1	26 JUN 01	03 AUG 01	156d												
CNNV2567	EBox-2 A/D-D/A Conv PWB Drill Drawing	2	27 FEB 02	28 FEB 02	8d												
CNNV2577	EBox-2 A/D-D/A Conv PWA Assy Drawing	3	01 MAR 02	05 MAR 02	15d												
CNNV2597	Procure EBox-2 A/D-D/A Conv PWB	10	01 MAR 02	14 MAR 02	8d												
CNNV2617	EBox-2 A/D-D/A Conv PWA Kitting & Traveler Prep	1	14 MAR 02	14 MAR 02	8d												
CNNV2627	EBox-2 A/D-D/A Conv PWA Assembly	3	15 MAR 02	19 MAR 02	8d												
CNNV2637	EBox-2 A/D-D/A Conv PWA Initial C/O & Tuning	2	20 MAR 02	21 MAR 02	8d												
CNNV2647	EBox-2 A/D-D/A Conv PWA Stand-Alone Verify	5	22 MAR 02	28 MAR 02	8d												
CNNV2512	Changeout LL Fit. D/A & A/D on EBox-2 PWA	3	29 MAR 02	02 APR 02	8d												
CNNV2518	ReTest EBox-2 A/D-D/A Conv PWA	3	03 APR 02	05 APR 02	8d												
EBox-3 / Digital Controller PWA																	
		167	26 JUN 01	08 APR 02	7d												
CNNV2651	FPGA & Non-Rad 1553 RT Procurement	64 *	26 JUN 01	01 NOV 01	89d												
CNNV2643	EBox-3 Digital Control PWA Schematic	5	29 JUN 01	09 AUG 01	14d												
CNNV2646	EBox-3 Digital Control PWB Layout	116 *	03 AUG 01	25 JAN 02	14d												
CNNV2655	EBox-3 Digital Control PWA PL	3	03 AUG 01	07 AUG 01	150d												
CNNV2649	EBox-3 Digital Control PWB Drill Drawing	2	28 JAN 02	29 JAN 02	14d												
CNNV2652	EBox-3 Digital Control PWA Assy Drawing	5	30 JAN 02	05 FEB 02	29d												
CNNV2658	Procure EBox-3 Digital Control PWB	10	30 JAN 02	12 FEB 02	14d												
CNNV2661	EBox-3 Digital Control PWB Coupon Test @ GSFC	10	13 FEB 02	26 FEB 02	14d												
CNNV2664	EBox-3 Digital Control PWA Kit & Traveler Prep	1	27 FEB 02	27 FEB 02	14d												
CNNV2667	EBox-3 Digital Control PWA Assembly	3	28 FEB 02	04 MAR 02	14d												
CNNV2670	EBox-3 Digital Control PWA Initial C/O & Tuning	7	05 MAR 02	13 MAR 02	14d												
CNNV1484	EBox-3 Digital Control PWA Verif Test Proc	10	11 MAR 02	22 MAR 02	7d												
CNNV2673	EBox-3 Digital Control PWA Stand-Alone Verify	5	25 MAR 02	29 MAR 02	7d												
CNNV2245	Changeout LL Fit. 1553 RT on Digital Control PWA	3	01 APR 02	03 APR 02	7d												

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001						2002					
						J	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN
CNNW2254	ReTest EBox-3 Digital Control PWA	3	04 APR 02	08 APR 02	7d												■ ReTest EBox-3 Dig
EBox-3 PWA FPGA																	
		50	03 AUG 01	12 OCT 01	103d												
CNNW2645	EBox-3 FPGA Design	20	03 AUG 01	30 AUG 01	103d												
CNNW2648	EBox-3 Digital Control FPGA Coding	30	31 AUG 01	12 OCT 01	103d												
EBox Assy & Test																	
		2	09 APR 02	10 APR 02	6d												
CNNW2233	Assemble 4-sides of EBox Enclosure	1	09 APR 02	09 APR 02	6d												■ Assemble 4-sides
CNNW2236	Temporary Stack EBox PWAs into Enclosure	1	10 APR 02	10 APR 02	6d												■ Temporary Stack
Intra-NWM Cables																	
		16	03 AUG 01	24 AUG 01	159d												
CNNW2820	Design RWS E-Box I/F Cable	5	03 AUG 01	09 AUG 01	159d												
CNNW2825	Design XTRK-EBox I/F Cable 1	5	03 AUG 01	09 AUG 01	159d												
CNNW2830	Design XTRK-EBox I/F Cable 2	5	03 AUG 01	09 AUG 01	159d												
CNNW2814	Complete RWS-EBox Cable Fab Dwgs	5	10 AUG 01	16 AUG 01	159d												
CNNW2819	Complete XTRK-EBox Cable Fab Dwgs 1	5	10 AUG 01	16 AUG 01	159d												
CNNW2824	Complete XTRK-EBox Cable Fab Dwgs 2	5	10 AUG 01	16 AUG 01	159d												
CNNW2817	Fabricate RWS-EBox I/F Cable	5	17 AUG 01	23 AUG 01	159d												
CNNW2822	Fabricate XTRK-EBox I/F Cable 1	5	17 AUG 01	23 AUG 01	159d												
CNNW2827	Fabricate XTRK-EBox I/F Cable 2	5	17 AUG 01	23 AUG 01	159d												
CNNW2811	Test RWS-EBox I/F Cable	1	24 AUG 01	24 AUG 01	159d												
CNNW2816	Test XTRK-EBox I/F Cable 1	1	24 AUG 01	24 AUG 01	159d												
CNNW2821	Test XTRK-EBox I/F Cable 2	1	24 AUG 01	24 AUG 01	159d												
NWM Parts Procurement																	
		98	01 MAY 01	02 JAN 02	148d												
CNNW2155	Select & Procure Magnet (Hourseshoe)	0	01 MAY 01	26 JUN 01													& Procure Magnet (Hourseshoe)
CNNV2854	Non-Rad 1553 RT & FPGA Procurement	64 *	26 JUN 01	01 NOV 01	92d												■ Non-Rad 1553 RT & FPGA Procurement
CNNW2135	Multiplier Procurement	40	26 JUN 01	28 SEP 01	126d												■ Multiplier Procurement
CNNW2252	RWS-4 Power Mosfets Procurement	26 *	26 JUN 01	10 SEP 01	137d												■ RWS-4 Power Mosfets Procurement
CNNW1260	Solenoid Procurement	40	03 AUG 01	28 SEP 01	17d												■ Solenoid Procurement
CNNW1312	Ferrite Cup Core Housing Procurement	20	03 AUG 01	30 AUG 01	141d												■ Ferrite Cup Core Housing Procurement
CNNW1480	Procure Shipping Container	13	03 AUG 01	21 AUG 01	233d												■ Procure Shipping Container
CNNW2158	Procure Ion Source Feedthrough & Ceramics	0	03 AUG 01	16 AUG 01													■ Procure Ion Source Feedthrough & Ceramics
CNNW2515	Receive D/A and A/D Flight Parts	0	03 DEC 01 *		85d												◆ Receive D/A and A/D Flight Parts
CNNW2290	Receive 1553 Flight Parts	0	02 JAN 02 *		70d												◆ Receive 1553 Flight Parts
NWM Assembly & Test																	
		71	10 APR 02	22 JUL 02	6d												■ NWM Subassemblies Complete
CNNW2833	NWM Subassemblies Complete	0		10 APR 02	6d												◆ NWM Subassemblies Complete



Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001					2002										
						AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV
CNNM1420	NVM System Testing	15	11 APR 02	01 MAY 02	6d																
CNNM1890	Need S/C Simulator *	0		30 APR 02	0																
CNNM1421	NVM System Calibration*	20	02 MAY 02	30 MAY 02	6d																
CNNM1493	Dis-Assemble NVM & pull PWA's	2	31 MAY 02	03 JUN 02	6d																
CNNM1496	PWA Cleaning & Final ONR Inspection	1	04 JUN 02	04 JUN 02	6d																
CNNM1499	PWA Staking & Cure	3	05 JUN 02	07 JUN 02	6d																
CNNM1502	Post PWA Staking Cleaning & Inspect	2	10 JUN 02	11 JUN 02	6d																
CNNM1505	PWA Warm-up & CC Dip / Cure	2	12 JUN 02	13 JUN 02	6d																
CNNM1508	NVM PWA Final Post-CC Inspect	1	14 JUN 02	14 JUN 02	6d																
CNNM1440	Final Flight Assembly *	5	17 JUN 02	21 JUN 02	6d																
CNNM1450	Final NVM End-Item Testing	20	24 JUN 02	22 JUL 02	6d																
NVM Environmental Testing																					
		22	23 JUL 02	21 AUG 02	25d																
CNNM1453	Prep & Transport to Env. Test Site	2	23 JUL 02	24 JUL 02	7d																
CNNM1456	NVM EMI/EMC Setup & Testing	5	25 JUL 02	30 JUL 02	7d																
CNNM1459	NVM Magnetic Induction Setup & Testing	2	31 JUL 02	01 AUG 02	7d																
CNNM1513	NVM EMI/EMC Test Report	5	31 JUL 02	06 AUG 02	35d																
CNNM1462	NVM Pre-Vibe Functional Testing	1	02 AUG 02	02 AUG 02	7d																
CNNM1507	NVM Mag Induction Test Report	5	02 AUG 02	08 AUG 02	34d																
CNNM1465	NVM Random Vibe (3-Axis) Setup & Testing	2	03 AUG 02	05 AUG 02	7d																
CNNM1468	NVM Shock Setup & Testing	1	06 AUG 02	06 AUG 02	7d																
CNNM1495	NVM Random Vibration Test Report	5	06 AUG 02	12 AUG 02	32d																
CNNM1477	NVM Post-Vibe Functional Testing	1	07 AUG 02	07 AUG 02	7d																
CNNM1498	NVM Shock Test Report	3	07 AUG 02	09 AUG 02	32d																
CNNM1471	NVM Thermal Vacuum Setup & Testing	7	08 AUG 02	14 AUG 02	8d																
CNNM1483	Post TV Ambient Functional Test	1	15 AUG 02	15 AUG 02	6d																
CNNM1501	NVM TV Test Report	5	15 AUG 02	21 AUG 02	25d																
CNNM1474	NVM Physical Properties	1	16 AUG 02	16 AUG 02	7d																
CNNM1489	Prep & Return NVM to UTD	1	17 AUG 02	17 AUG 02	8d																
CNNM1486	Burn-In Functional Test (Meet Cum 200 Hrs.)	2	19 AUG 02	20 AUG 02	5d																
CNNM1504	NVM Physical Properties Report	3	19 AUG 02	21 AUG 02	25d																
BCE/GSE Test Equipment																					
		100	01 JUN 01	03 JAN 02	158d																
Electronics																					
		31	01 JUN 01	17 SEP 01	139d																
CNNM1200	BCE/GSE Elec Design/Schematic	0 *	01 JUN 01	22 JUN 01																	
CNNM1203	BCE/GSE PWB Layout	0	25 JUN 01	27 JUN 01																	
CNNM1254	BCE/GSE IPL	1	26 JUN 01	03 AUG 01	154d																

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001																								2002			
						JUL				AUG				SEP				OCT				NOV				DEC				JAN			
						23	30	06	13	20	27	03	10	17	24	01	08	15	22	29	05	12	19	26	02	09	16	23	30	06	13	20	27
CNNW1210	RWS BCE PWA Assembly/Test	15	13 AUG 01	31 AUG 01	149d																												
CNNW1265	NVM GSE PWA Assembly/Test	15	13 AUG 01	31 AUG 01	149d																												
CNIV1268	IVM GSE PWA Assembly/Test	15	20 AUG 01	10 SEP 01	142d																												
CNNW1240	XTRK BCE PWA Assembly/Test	20	20 AUG 01	17 SEP 01	139d																												
Cables																																	
		20	03 AUG 01	30 AUG 01	238d																												
CNIV1558	Design/Fab EMI-specific Cables	5	03 AUG 01	09 AUG 01	220d																												
CNIV1681	Design/Fab TV-specific Cables	10	03 AUG 01	16 AUG 01	224d																												
CNNW1245	RWS BCE Test Cable Design	2	03 AUG 01	06 AUG 01	163d																												
CNNW1251	XTRK BCE Test Cable Design	10	03 AUG 01	16 AUG 01	150d																												
CNNW1283	NVM GSE Test Cable Design	2	03 AUG 01	06 AUG 01	163d																												
CNNW1286	IVM GSE Test Cable Design	10	03 AUG 01	16 AUG 01	153d																												
CNNW1460	Design/Fab TV-specific Cables	10	03 AUG 01	16 AUG 01	248d																												
CNNW1525	Design/Fab EMI-specific Cables	7	03 AUG 01	13 AUG 01	241d																												
CNNW1248	RWS BCE Test Cable Fab/Assy/Test	5	07 AUG 01	13 AUG 01	163d																												
CNNW1293	NVM GSE Test Cable Fab/Assy/Test	5	07 AUG 01	13 AUG 01	163d																												
CNIV1296	IVM GSE Test Cable Fab/Assy/Test	5	17 AUG 01	23 AUG 01	153d																												
CNNW1272	XTRK BCE Test Cable Fab/Assy/Test	10	17 AUG 01	30 AUG 01	150d																												
Mechanical																																	
		40	06 JUL 01	28 SEP 01	130d																												
CNNW1142	Mech RWS BCE Detailed System Design	0	06 JUL 01	19 JUL 01																													
CNNW1154	Mech XTRK BCE Detailed System Design	0	06 JUL 01	19 JUL 01																													
CNNW1139	Mech IVM/NVM GSE System Design	0	09 JUL 01	20 JUL 01																													
CNNW1141	Mech IVM/NVM GSE Detailed Design	20	03 AUG 01	30 AUG 01	128d																												
CNNW1148	RWS BCE Mech Fab/Assy	0	03 AUG 01	16 AUG 01																													
CNNW1151	XTRK BCE Mech Fab/Assy	0	03 AUG 01	16 AUG 01																													
CNIV1236	IVM GSE Mech Fab/Assy	10	17 SEP 01	28 SEP 01	128d																												
CNNW1233	NVM GSE Mech Fab Mods/Assy	10	17 SEP 01	28 SEP 01	130d																												
GSE Software																																	
		95	26 JUN 01	18 DEC 01	78d																												
CNIV1516	IVM GSE Software	95	26 JUN 01	18 DEC 01	78d																												
CNNW1136	NVM GSE Software	95	26 JUN 01	18 DEC 01	75d																												
BCE/GSE Procurement																																	
		30	03 AUG 01	28 SEP 01	128d																												
CNIV2721	Procure IVM Connector Saver's	0	03 AUG 01	28 SEP 01																													
CNNW1145	BCE COTS Enclosure Procure	0	03 AUG 01	16 AUG 01																													
CNNW1220	BCE/GSE PWB Fabrication	6	03 AUG 01	10 AUG 01	144d																												
CNNW2521	Procure NVM Connector Saver's	0	03 AUG 01	28 SEP 01																													

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001												2002											
						AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL
CNNW1257	Procure RWS BCE Piece Parts	0	06 AUG 01	31 AUG 01																									
CNNW1230	GSE COTS Enclosure Procure	10	31 AUG 01	14 SEP 01	128d																								
BCE/GSE Assembly & Test																													
		79	04 SEP 01	03 JAN 02	75d																								
CNNW1213	RWS BCE Final Assy	5	04 SEP 01	10 SEP 01	149d																								
CNNW1216	XTRK BCE Final Assy	5	18 SEP 01	24 SEP 01	139d																								
CNIV1242	IVM GSE Final Assy	5	01 OCT 01	05 OCT 01	128d																								
CNNW1239	NWM GSE Final Assy	5	19 DEC 01	03 JAN 02	75d																								
NWM Delivery																													
		23	21 AUG 02	23 SEP 02	5d																								
CNNW1510	NWM Schedule Reserve Contingency	22	21 AUG 02	20 SEP 02	5d																								
CNNW1492	Pack & Ship NWM to KAFO	1	23 SEP 02	23 SEP 02	5d																								
Specifications / Documentation / Analysis																													
		40	01 JUN 01	28 SEP 01	47d																								
CNNW1263	Preliminary NWM ICD	0 *	01 JUN 01	13 AUG 01																									
CNNW1576	Prelim NWM Thermal Analysis	0 *	09 JUL 01	07 AUG 01																									
CNA11104	CINDI NWM FMEA	40	03 AUG 01	28 SEP 01	47d																								
CNA11110	Preliminary NWM EEE Parts List	0	03 AUG 01	16 AUG 01																									
CNA11116	Preliminary NWM Materials List	0	03 AUG 01	16 AUG 01																									
CNA11125	CINDI Contamination Control Plan	5	03 AUG 01	09 AUG 01	67d																								
CNNW1266	Final NWM ICD Modifications	30	03 AUG 01	14 SEP 01	9d																								
CNNW1579	Prelim NWM Mechanical Stress Analysis	10	03 AUG 01	16 AUG 01	29d																								
CNNW1582	Final NWM Thermal Analysis	21	03 AUG 01	31 AUG 01	18d																								
CNNW1585	Final NWM Mechanical Stress Analysis	16	04 SEP 01	25 SEP 01	18d																								
Review Preparation & Support																													
		76	31 MAY 02	17 SEP 02	8d																								
CNNW1540	Pre-Environmental Review @ UTD-NWM Prep	10	31 MAY 02	13 JUN 02	31d																								
CNNW1543	NWM Pre-Environmental Review (PER)	1	14 JUN 02	14 JUN 02	31d																								
CNNW1560	Pre-Ship Rev/Func Conf Audit @ UTD-NWM Prep	10	03 SEP 02 *	16 SEP 02	8d																								
CNNW1563	NWM Pre-Ship Review (PSR) @ UTD	1	17 SEP 02	17 SEP 02	8d																								
NWM Verification / Procedures																													
		40	03 AUG 01	28 SEP 01	224d																								
CNA11128	NWM Verification Matrix	20	03 AUG 01	30 AUG 01	67d																								
CNA11134	NWM Environmental Test Matrix	20	03 AUG 01	30 AUG 01	67d																								
CNA11143	Draft NWM Verification Procedures	40	03 AUG 01	28 SEP 01	47d																								
CNA11149	Final NWM Verification Procedures	1	03 AUG 01	03 AUG 01	244d																								
CNIV2851	NWM EIT Vac Test Proc @ Ambient w/lon Source	1	03 AUG 01	03 AUG 01	189d																								

	Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001																								2002																																						
							JUL							AUG							SEP							OCT							NOV							DEC							JAN							FEB							MAR						
							23	30	06	13	20	27	03	10	17	24	01	08	15	22	29	05	12	19	26	03	10	17	24	31	07	14	21	28	04	11	18	25	04	11																													
	CNNM1427	NVM EIT Functional Test Proc (Over Temp)	20	03 AUG 01	30 AUG 01	155d																																																															
	CNNM1433	NVM EIT Calibration Proc (Over Temp)	40	03 AUG 01	28 SEP 01	150d																																																															
	CNNM1436	NVM EMI/EMC Test Procedure	20	03 AUG 01	30 AUG 01	228d																																																															
	CNNM1439	NVM Magnetic Induction Test Proc	20	03 AUG 01	30 AUG 01	232d																																																															
	CNNM1442	NVM Random Vibe & Shock Test Proc	20	03 AUG 01	30 AUG 01	234d																																																															
	CNNM1445	NVM TV Test Proc	30	03 AUG 01	14 SEP 01	228d																																																															
	CNNM1448	NVM Physical Properties Procedure	5	03 AUG 01	09 AUG 01	259d																																																															
Education / Public Outreach																																																																					
			510	02 JUN 03	14 JUN 05	12d																																																															
	CNA11073	Teacher Workshop in Dallas, TX	10	02 JUN 03 *	13 JUN 03	492d																																																															
	CNA11076	Teacher Workshop in Victoria, TX	10	01 JUN 04 *	14 JUN 04	252d																																																															
	CNA11079	Teacher Workshop in Victoria, TX	10	01 JUN 05 *	14 JUN 05	12d																																																															
Ion Velocity Meter (IVM) Development																																																																					
			266	01 JUN 01	27 AUG 02	3d																																																															
IVM Instrument																																																																					
			266	01 JUN 01	27 AUG 02	3d																																																															
IVM Design & Fabrication																																																																					
			146	26 JUN 01	08 MAR 02	78d																																																															
IVM Drift Meter (DM)																																																																					
			49	26 NOV 01	11 FEB 02	42d																																																															
DM Housing & Mechanical Details																																																																					
			23	26 NOV 01	04 JAN 02	6d																																																															
	CNIV1080	IVM DM Sensor Mechanical Design/Dwgs	23	26 NOV 01	04 JAN 02	6d																																																															
DM Sensor Assembly & Test																																																																					
			6	04 FEB 02	11 FEB 02	42d																																																															
	CNIV2848	Assemble DM Grid, Ring, & Grid Mounts (x7) Trim	4	04 FEB 02	07 FEB 02	42d																																																															
	CNIV2836	Stack Grids (5) & Collector Plates (4) on DM B/P	1	08 FEB 02	08 FEB 02	42d																																																															
	CNIV2710	Complete Final Assembly of DM Sensor	1	11 FEB 02	11 FEB 02	42d																																																															
IVM Retarding Potential Analyzer (RPA)																																																																					
			40	07 JAN 02	01 MAR 02	28d																																																															
RPA Housing & Mechanical Details																																																																					
			15	07 JAN 02	25 JAN 02	23d																																																															
	CNIV2646	IVM RPA Sensor Mechanical Design/Dwgs	15	07 JAN 02	25 JAN 02	23d																																																															
RPA Sensor Assembly & Test																																																																					
			5	25 FEB 02	01 MAR 02	28d																																																															

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001												2002																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
						JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
CNIV2619	Assemble RPA Grid, Ring, & Grid Mounts (x6) Trim	3	25 FEB 02	27 FEB 02	28d																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		</



Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001												2002												
						J	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL
CNIV2818	Procure IVM-3 Digital Control PWB	10	30 NOV 01	13 DEC 01	53d																									
CNIV2821	IVM-3 Digital Control PWB Coupon Test @ GSFC	10	14 DEC 01	07 JAN 02	53d																									
CNIV2824	IVM-3 Digital Control PWA Kit & Traveler Prep	1	08 JAN 02	08 JAN 02	53d																									
CNIV2827	IVM-3 Digital Control PWA Assembly	3	09 JAN 02	11 JAN 02	53d																									
CNIV2830	IVM-3 Digital Control PWA Initial C/O & Tuning	7	14 JAN 02	22 JAN 02	53d																									
CNIV2833	IVM-3 Digital Control PWA Stand-Alone Verify	5	23 JAN 02	29 JAN 02	53d																									
IVM-3 PWA FPGA																														
		50	03 AUG 01	12 OCT 01	106d																									
CNIV2797	IVM-3 Digital Cntrl FPGA Design	20	03 AUG 01	30 AUG 01	106d																									
CNIV2806	IVM-3 Digital Cntrl FPGA Coding	30	31 AUG 01	12 OCT 01	106d																									
IVM Mechanical																														
		45	07 JAN 02	08 MAR 02	25d																									
CNIV2625	IVM DM Sensor Housing Machine & Plate	20	07 JAN 02	01 FEB 02	46d																									
CNIV2640	IVM DM Details Machine & Plate	20	07 JAN 02	01 FEB 02	6d																									
CNIV2622	IVM RPA Sensor Housing Machine & Plate	20	28 JAN 02	22 FEB 02	31d																									
CNIV2637	IVM RPA Details Machine & Plate	20	28 JAN 02	22 FEB 02	28d																									
CNIV2643	IVM Packaging Design/Dwgs	10	28 JAN 02	08 FEB 02	23d																									
CNIV2628	IVM Mech Standoffs & Details Machine & Plate	20	11 FEB 02	08 MAR 02	25d																									
CNIV2631	IVM Baseplate Machine & Plate	20	11 FEB 02	08 MAR 02	23d																									
CNIV2634	IVM Housing Machine & Plate	20	11 FEB 02	08 MAR 02	25d																									
IVM Parts Procurement																														
		15	26 JUN 01	23 AUG 01	209d																									
CNIV2845	GRID Material Procurement	0	26 JUN 01	26 JUN 01																										
CNIV1678	Procure Shipping Container	15	03 AUG 01	23 AUG 01	209d																									
IVM Assembly & Test																														
		55	11 MAR 02	27 MAY 02	23d																									
CNIV2719	Mount DM & RPA Sensor SubAssy's to IVM	1	11 MAR 02	11 MAR 02	23d																									
CNIV2712	Connect Feed Thru Wires & Route (x7)	1	12 MAR 02	12 MAR 02	23d																									
CNIV2718	Stack up PWA's & Temp Solder Wire Connects	1	13 MAR 02	13 MAR 02	23d																									
CNIV2727	Complete IVM Enclosure/Cover	1	14 MAR 02	14 MAR 02	23d																									
CNIV1537	IVM System Testing	11	15 MAR 02	29 MAR 02	23d																									
CNIV1663	Need S/C Simulator *	0		15 MAR 02	0																									
CNIV1540	IVM System Calibration*	15	01 APR 02	19 APR 02	23d																									
CNIV1612	Dis-Assemble IVM & pull PWA's	2	22 APR 02	23 APR 02	23d																									
CNIV1618	PWA Cleaning & Final ONR Inspection	1	24 APR 02	24 APR 02	23d																									
CNIV1624	PWA Staking & Cure	2	25 APR 02	26 APR 02	23d																									
CNIV1630	Post PWA Staking Cleaning & Inspect	1	29 APR 02	29 APR 02	23d																									
CNIV1636	PWA Warm-up & CC Dip / Cure	2	30 APR 02	01 MAY 02	23d																									

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001					2002									
						AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT
CNIV1642	IVM PWA Final Post-CC Inspect	1	02 MAY 02	02 MAY 02	23d															IVM PWA Final Post-CC Inspect
CNIV1555	Final IVM Flight Assembly *	3	03 MAY 02	08 MAY 02	23d															Final IVM Flight Assembly *
CNIV1567	Final IVM End-Item Tests *	13	09 MAY 02	27 MAY 02	23d															Final IVM End-Item Tests *
IVM Environmental Testing																				
		23	28 MAY 02	27 JUN 02	43d															
CNIV1570	Prep & Transport IVM to Env. Test Site	2	28 MAY 02	29 MAY 02	27d															Prep & Transport IVM to Env.
CNIV1573	IVM EMI/EMC Setup & Testing	3	30 MAY 02	01 JUN 02	27d															IVM EMI/EMC Setup & Testing
CNIV1576	IVM Magnetic Induction Setup & Testing	2	03 JUN 02	04 JUN 02	27d															IVM Magnetic Induction Setup
CNIV1648	IVM EMI/EMC Test Report	5	03 JUN 02	07 JUN 02	56d															IVM EMI/EMC Test Report
CNIV1582	IVM Pre-Vibe Functional Testing	1	05 JUN 02	05 JUN 02	27d															IVM Pre-Vibe Functional Test
CNIV1639	IVM Mag Induction Test Report	5	05 JUN 02	11 JUN 02	55d															IVM Mag Induction Test Report
CNIV1585	IVM Random Vibe (3-Axis) Setup & Testing	2	06 JUN 02	07 JUN 02	27d															IVM Random Vibe (3-Axis) Setup
CNIV1588	IVM Shock Setup & Testing	1	08 JUN 02	08 JUN 02	27d															IVM Shock Setup & Testing
CNIV1597	IVM Post-Vibe Functional Testing	1	10 JUN 02	10 JUN 02	27d															IVM Post-Vibe Functional Test
CNIV1615	IVM Random Vibration Test Report	5	10 JUN 02	14 JUN 02	52d															IVM Random Vibration Test Report
CNIV1621	IVM Shock Test Report	3	10 JUN 02	12 JUN 02	53d															IVM Shock Test Report
CNIV1591	IVM Thermal Vacuum Setup & Testing	7	11 JUN 02	17 JUN 02	31d															IVM Thermal Vacuum Setup
CNIV1600	IVM Post TV Ambient Functional Test	1	18 JUN 02	18 JUN 02	27d															IVM Post TV Ambient Functional
CNIV1627	IVM TV Test Report	5	18 JUN 02	24 JUN 02	46d															IVM TV Test Report
CNIV1594	IVM Physical Properties	1	19 JUN 02	19 JUN 02	27d															IVM Physical Properties
CNIV1606	Prep & Return IVM to UTD	1	20 JUN 02	20 JUN 02	32d															Prep & Return IVM to UTD
CNIV1633	IVM Physical Properties Report	2	20 JUN 02	21 JUN 02	47d															IVM Physical Properties Report
CNIV1603	IVM Burn-In Functional Test (Meet Cum 200 Hrs.)	5	21 JUN 02	27 JUN 02	22d															IVM Burn-In Functional Test
IVM Delivery																				
		42	28 JUN 02	27 AUG 02	3d															
CNIV1645	IVM Schedule Reserve Contingency	22	28 JUN 02	30 JUL 02	22d															IVM Schedule Reserve Contingency
CNIV1609	Pack & Ship IVM to KAFD	1	27 AUG 02	27 AUG 02	3d															Pack & Ship
Specifications / Documentation / Analysis																				
		63	01 JUN 01	31 OCT 01	18d															
CNIV1273	Preliminary IVM ICD	7 *	01 JUN 01	13 AUG 01	1d															Preliminary IVM ICD
CNIV1279	Prelim IVM Thermal Analysis	0 *	09 JUL 01	07 AUG 01																Prelim IVM Thermal Analysis
CNA11101	CINDI IVM FMEA	40	03 AUG 01	28 SEP 01	32d															CINDI IVM FMEA
CNA11107	Preliminary IVM EEE Parts List	0	03 AUG 01	16 AUG 01																Preliminary IVM EEE Parts List
CNA11113	Preliminary IVM Materials List	0	03 AUG 01	16 AUG 01																Preliminary IVM Materials List
CNIV1282	Prelim IVM Mechanical Stress Analysis	10	03 AUG 01	16 AUG 01	60d															Prelim IVM Mechanical Stress Analysis
CNIV1276	Final IVM ICD Modifications	30	14 AUG 01	25 SEP 01	2d															Final IVM ICD Modifications
CNIV1285	Final IVM Thermal Analysis	15	26 SEP 01	16 OCT 01	18d															Final IVM Thermal Analysis
CNIV1288	Final IVM Mechanical Stress Analysis	11	17 OCT 01	31 OCT 01	18d															Final IVM Mechanical Stress Analysis

Act ID	Activity Description	Rem Dur	Early Start	Early Finish	Total Float	2001					2002											
						AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT		
Review Preparation & Support																						
		85	26 APR 02	26 AUG 02	3d																	
CNIV1651	Pre-Environmental Review @ UTD-IVM Prep	10	26 APR 02	10 MAY 02	33d																	
CNIV1654	IVM Pre-Environmental Review (PER)	1	13 MAY 02	13 MAY 02	33d																	
CNIV1657	Pre-Ship Rev/Func Conf Audit @ UTD-IVM Prep	10	12 AUG 02	23 AUG 02	3d																	
CNIV1660	IVM Pre-Ship Review (PSR) @ UTD	1	26 AUG 02	26 AUG 02	3d																	
IVM Verification / Procedures																						
		191	03 AUG 01	13 MAY 02	48d																	
CNIV1672	IVM TV Test Proc	20	03 AUG 01	30 AUG 01	214d																	
CNIV1675	IVM Physical Properties Procedure	10	03 AUG 01	16 AUG 01	229d																	
CNIV2701	IVM-1 RPA/DM PWA Verif Test Proc	40	03 AUG 01	28 SEP 01	126d																	
CNIV2704	IVM-2 LVPS/RV Gen PWA Verif Test Proc	40	03 AUG 01	28 SEP 01	126d																	
CNIV2707	IVM-3 Digital Control PWA Verif Test Proc	10	03 AUG 01	16 AUG 01	156d																	
CNA11137	Draft IVM Verification Procedures	40	04 SEP 01 *	29 OCT 01	26d																	
CNA11122	IVM Verification Matrix	20	01 OCT 01	26 OCT 01	27d																	
CNA11131	IVM Environmental Test Matrix	20	01 OCT 01	26 OCT 01	27d																	
CNIV1543	IVM EIT Functional Test Proc (Over Temp)	20	03 DEC 01 *	08 JAN 02	70d																	
CNIV1546	IVM EIT Calibration Proc (Over Temp)	40	03 DEC 01 *	05 FEB 02	61d																	
CNIV1507	IVM EIT Vac Test Proc @ Ambient	20	02 JAN 02 *	29 JAN 02	93d																	
CNA11146	Final IVM Verification Procedures	40	15 MAR 02	10 MAY 02	33d																	
CNIV1552	IVM Magnetic Induction Test Proc	20	01 APR 02	26 APR 02	47d																	
CNIV1669	IVM Random Vibe Proc	20	01 APR 02	26 APR 02	49d																	
CNIV1549	IVM EMI/EMC Test Procedure	20	15 APR 02	13 MAY 02	34d																	
CINDI Project Level Activity																						
		1373	02 APR 01	12 JAN 07	0																	
CNA01480	Preliminary Reliability/Safety Documentation	9 *	02 APR 01	15 AUG 01	3d																	
CNA11053	USAF PDR Preparation	0 *	16 JUL 01	30 JUL 01																		
CNA11056	USAF PDR @ UTD	0	31 JUL 01	31 JUL 01																		
CNA11062	NASA PDR @ UTD	1	03 AUG 01	03 AUG 01	17d																	
CNA11083	Preliminary PRA Statement by Aerospace	0	03 AUG 01	23 AUG 01																		
CNA11095	Perf Assurance Implementation Plan	21	03 AUG 01	31 AUG 01	0																	
CNA11098	CINDI Level 1 Program Requirements Document	0	03 AUG 01	14 SEP 01																		
CNA11077	CINDI Confirmation Review @ UTD	1	06 AUG 01	06 AUG 01	18d																	
CNA11059	NASA PDR Preparation	0	14 AUG 01	27 AUG 01																		
CNA01483	Final Reliability/Safety Documentation	80	16 AUG 01	10 DEC 01	3d																	
CNA11086	Final PRA by Aerospace	20	01 NOV 01	30 NOV 01	9d																	
CNA11065	USAF CDR Preparation	15	05 NOV 01	27 NOV 01	1d																	
CNA11068	USAF CDR @ UTD	1	28 NOV 01	28 NOV 01	1d																	







# **PROJECT MANAGEMENT - RISK MANAGEMENT**

(CINDI Plan based on GSFC plan)

- Risk Identification
  - Full team participation
  - All project elements and phases
  - Formulate risk statements
- Risk Assessment
- Risk Planning
  - Research
  - Accept
  - Watch
  - Mitigate
- Risk Monitoring
- Risk Handling
  - Control
  - Communication/documentation

CINDI CRM  
RISK ASSESSMENT

- Risk Assessment
  - Assess likelihood of occurrence
  - Assess consequence to the project
  - Classify (score) risk

		RISK CATEGORIZATION		
		1	2	3
LIKELIHOOD (P)	Very Likely (HIGH) 3	4	5	6
	Probable (MEDIUM) 2	3	4	5
	Improbable (LOW) 1	2	3	4
		1 Marginal (LOW)	2 Critical (MEDIUM)	3 Severe (HIGH)
		CONSEQUENCE (C)		

$C + P = (score)$

CINDI CRM  
RISK MONITORING

- Continuous assessment of risk reduction
- Track mitigation effectiveness
- Ensure risk retirement/acceptable mitigation

CINDI RISK WATCH LIST							
RISK NUMBER	RISK NAME	RISK OWNER	RISK DESCRIPTION	MITIGATION PLAN	SCORE		TIME FRAME
					W/O MITIGATION	W/ MITIGATION	

- 
- Risk Handling
    - SE is the focal point for technical risk management
    - PM manages schedule and cost risk
    - Risk Management Board (RMB)
      - Meets at least monthly
      - PM, SE, RQA, GSE, Mechanical, Electrical, Science/Software Representatives
  - RMB Actions
    - Continue current mitigation plan
    - Review/revise watch list
    - Re-plan
    - Close risk
    - Invoke a contingency plan

## TOP FIVE RISKS

RISK RANK	RISK NAME	RISK OWNER	RISK DESCRIPTION	MITIGATION PLAN	SCORE	
					W/OUT MITIGATION	W/ MITIGATION
1	Schedule- Documentation and Review Requirements	PM	NASA documentation and review requirements could overload manpower effort of key personnel at critical times resulting in a schedule slip.	1. Carefully consider value and impact of added documentation and/or changes to UTD traditional approach in light of required delivery date. 2. Delay delivery of documentation to the extent permitted. 3. Obtain SwRI Assistance. 4. Hire experienced RQA engineer. 5. Develop resource loaded schedule. 6. Subcontracted PRA effort.	2+2=(4)	2+1=(3)
2	Schedule - Late Flight Parts Delivery	PM	Long lead times for parts delivery could cause a schedule slip.	1. Long lead parts identified and ordered. 2. Procure work-around parts. 3. Use existing inventories 4. Facilitate timely NASA funding. 5. Begin test cycle with low-rel part, replace with Hi-rel, retest as required.	2+2=(4)	2+1=(3)
3	Multiplier Failure	SE	Multiplier failure causes loss of RWS data.	1. Use mechanically robust multiplier. 2. Do early vibration test 3. Use long lifetime multiplier. 4. Provide clean vacuum environment during test and flight 5. Dry nitrogen backfill during integration/testing.	2+2=(4)	2+1=(3)
4	Filament Failure	SE	Filament failure causes loss of RWS or XTRK data.	1. Provide redundant filaments. 2. Use soft start circuit for filament heat 3. Current limit filament heat output 4. Use long-life with high efficiency to reduce heat 5. Do early performance/validation tests. 6. Use minimum required emission current 7. Provide filament disable plug for protection during ground test 8. Performed extensive filament lifetime analysis.	2+2=(4)	2+1=(3)
5	PE Valve Failure	SE	PE Valve failure results in inability to equalize pressures in NWM sensor pressure chambers.	1. Use solenoid design with minimal moving parts. 2. Spring load to closed position. 3. Use dry lubricant on solenoid plunger. 4. Life test and early vibration test.	2+2=(4)	1+1=(2)



---

<u>DESCOPE OPTION</u>	<u>SCIENCE IMPACT</u>
1. Give NWM priority over IVM	1. None, Possible late IVM delivery
2. Descope(remove) RPA	2. 20% loss, min. C/NOFS impact
3. Descope(remove) IVM	3. 30% loss, min. C/NOFS impact
4. Descope(remove) CTS	4. 50% loss, substantial C/NOFS mission impact

# DESCOPE PROCESS LINKAGES

---

- Technical – no state-of-the art items, prior instrument development/test
- Budget - well funded with margin during critical time periods
  - Facilitates possibility of offloading to outside subcontractor
  - Facilitates possibility of acquiring additional personnel resources
- Conclusion - Descope considerations most likely triggered by schedule issues

DESCOPE/SCHEDULE  
LINKAGE

---

TRIGGER	POSSIBLE ACTIONS
<ul style="list-style-type: none"><li>• Schedule slippage on subsystem critical path for delivery to next assembly for 2 consecutive reporting periods or total negative float &gt; 10 days</li></ul>	<ul style="list-style-type: none"><li>• Identify problem</li><li>• Descope subsystem where possible</li><li>• Augment staffing</li><li>• Move work to outside vendor</li><li>• Implement descope option 1</li></ul>
<ul style="list-style-type: none"><li>• Schedule slippage on subsystem critical path for delivery to next assembly for 2 consecutive reporting periods or total negative float &gt; 20 days</li></ul>	<ul style="list-style-type: none"><li>• Implement descope options 2, 3, or 4 as appropriate</li></ul>

Descope options executed with concurrence of both the NASA &  
C/NOFS project offices

- PRA performed by Aerospace Corp.
- GSFC contract direct to Aerospace
- PRA analysis of all of CINDI hardware
- Does not include PRA analysis of C/NOFS spacecraft or mission

- 
- Identify most critical CINDI components
  - Rank mission critical components according to risk contribution
  - Estimate likelihood of CINDI success per PRA

- 
- Functional FMEA 30 Nov 01
  - Develop and quantify PRA models
    - Preliminary results by 30 Nov 01
    - Final completed by 31 Jan 02
  - Identify and rank main risk contributors
    - Preliminary results by 15 Dec 01
    - Final completed by 28 Feb 02

# **PROJECT MANAGEMENT - REVIEW PROCESS**

- 
- In-house UTD reviews
    - Reviews of subsystems and instruments
    - Experienced scientists and engineers
  - Air Force and Spectrum Astro reviews of NWM & IVM
  - GSFC will enlist discipline experts to review circuit designs of NWM & IVM



- 
- |                                  |           |
|----------------------------------|-----------|
| • Phase A Report Review          | 10 May 01 |
| • Air Force PDR                  | 31 Jul 01 |
| • NASA PDR                       | 28 Aug 01 |
| • NASA Confirmation Review       | 29 Aug 01 |
| • Air Force CDR                  | 29 Nov 01 |
| • NASA CDR                       | Dec 01    |
| • Pre-Environmental Review - IVM | Aug 02    |
| • Pre-Ship Review - IVM          | Aug 02    |
| • Pre-Environmental Review - NWM | Sept 02   |
| • Pre-Ship Review - NWM          | Oct 02    |
| • Ground Operations Review       | Jan 03    |
| • Flight Readiness Review        | Oct 03    |
-

---

## UTD In-House Peer Reviews

- Perform early vibration of multiplier assy - Nov 01
- Include dry nitrogen backfill for NWM - CLOSED
- Enlist SwRI to provide documentation jump-start - CLOSED
- Utilize redundant filaments in RWS and XTRK - CLOSED
- Current limit filament heat - CLOSED
- Perform detailed analysis and literature investigation on filament lifetime - CLOSED
- Perform early performance/validation tests of filament - Sept 01
- Provide range of emission to operate filament at minimum required emission on orbit - CLOSED
- Investigate and convert to solenoid instead of motor in XTRK sensor - CLOSED
- Perform early vibration and accelerated life test on solenoid assy - Nov 01

---

## Phase A Report Review

- Check lead-time of tantalum capacitors - CLOSED
- Work with NASA IV&V facility to produce letter for NASA HQ - CLOSED
- GSFC to provide UTD with Interpoint Converter information - CLOSED
- Investigate Aerospace support to perform PRA - CLOSED

## Air Force PDR


- Perform magnetic measurements of RWS source magnet - 15 Sept 01
- Provide updated EMI/EMC data from spec sheets on internal instrument components - CLOSED
- Provide minimum bend radius for NWM S/C I/F cables - 15 Sept 01
- Provide drawings/definition of NWM safing screw and alignment mirrors - CLOSED
- Provide cleanliness requirement for SV thermal vac chamber - CLOSED

- 
- Current - Draft ICDs are under Spectrum Astro configuration management/revision control
  - 24 Sept 01 (after Mission PDR) - AFRL and UTD sign preliminary ICDs
  - Mid-December 01 - Final ICDs signed by all parties (AFRL, UTD, STP, Spectrum)

---

# SYSTEMS ENGINEERING

- 
- UTD Systems Engineer(SE) is responsible for all instrument performance and interface requirements and verification
  - SE tracks technical resource (mass,power,TM,etc) utilization/margins as allocated in the ICD
  - SE was on C/NOFS S/C Source Selection Advisory Board – familiar with C/NOFS S/C, instrument accommodation and interface issues
  - SE tracks instrument performance and interface progress/status via the following:
    - Daily interaction with UTD team members
    - Weekly UTD team meetings
    - Weekly C/NOFS IPT telecon
    - In-house reviews of instruments/subsystems
    - Frequent communication with C/NOFS SE and S/C contractor
-



## NOTES:

1. ICD & Instrument Requirements Document contain verification matrices
2. IRD specifies instrument measurement requirements
3. ICD controls all instrument/spacecraft interfaces and allocates resources
4. MRD controlled by Air Force
5. ICD controlled by Spectrum Astro
6. IRD controlled by UTD

\* not maintained

SCIENCE MEASUREMENT  
REQUIREMENTS

---

**PRIMARY MEASUREMENTS**

Source: CINDI Proposal and C/NOFS Science

Parameter	Dynamic Range	Accuracy
1. Ion Drift Vector	-500 m/s to +500 m/s	$\pm 2$ m/s
2. Neutral Wind Vector	-500 m/s to + 500 m/s	$\pm 10$ m/s

**SECONDARY MEASUREMENTS**

Source: C/NOFS and CINDI Science

Parameter	Dynamic Range	Accuracy
3. Total Ion Concentration	50 to $5 \times 10^6$ cm <sup>-3</sup>	1%
4. Ion Temperature	500 to 7000 K	50 K



---

PARAMETER	DYNAMIC RANGE
5. Total Ion Concentration	50 to $5 \times 10^6 \text{ cm}^{-3}$
6. Ion Mass Range	1 to 32 amu
7. Ion Temperature	500 to 7000 K
8. Total Neutral Concentration	$6 \times 10^6$ to $6 \times 10^8 \text{ cm}^{-3}$
9. Neutral Mass Range	4 to 16 amu
10. Neutral Temperature	500 to 4000 K

---

FLOW DOWN REQUIREMENTS  
ENGINEERING MEASUREMENTS

---

Source #	Parameter	Value
3,5	RPA Current Range	$3 \times 10^{-11}$ to $3 \times 10^{-6}$ A
3	RPA Current Accuracy	1 %
6,7	Max RPA R.V.	19 V
1,4	RPA R.V. Accuracy	3 mV
1,5	IDM Current Range	$5 \times 10^{-12}$ to $6 \times 10^{-7}$ A
1	IDM Max Current Ratio	1.2
1	IDM Curr Ratio Resolution	1.0003
8,10	RWS Current Range	$4 \times 10^{-12}$ to $4 \times 10^{-9}$ A
8,9,10	Max RWS R.V.	10 V
2,10	RWS R.V. Accuracy	7 mV
2,8,10	XTRK Current Range	$3 \times 10^{-12}$ to $3 \times 10^{-9}$ A
2	XTRK Max Current Ratio	1.1
2	XTRK Current Ratio Resolution	1.0005

---

- 
- Instrument Requirements Document(IRD) - documents instrument science and engineering measurement requirements, flowdown, dynamic range, accuracy - contains verification matrix
  - Instrument ICD – captures all interface requirements , resource allocation and margins, and environmental test/verification requirements for each instrument - contains verification matrix

- 
- Thermal Cycles
    - 8 Cycles
    - -24C to +61C
  - Random Vibration
    - 9.0 GRMS
    - 140 seconds
    - Protoflight levels per ICD
  - Pyroshock (1 shock per axis)
    - Protoflight Levels (2000 peak g) per ICD
  - Thermal Vacuum
    - 8 Cycles
    - -24C to +61C (operation)
    - -34C to +71C (survival)
  - EMI/EMC
    - Internal SC Bus per ICD
  - Test sequence follows ICD
  - Magnetic induction test
  - Test procedures will be written by UTD or by test vendors with UTD input and approval

- 
- Thermal control scheme and limits
  - Spacecraft mounting scheme
  - Alignment method/requirements
  - 1553 data and command interface
  - Power interface
  - Contamination control requirements

---

# VERIFICATION

- IRD Requirements Verification
  - Science/Measurement Environment Flowdown
    - Verified by analysis
  - Engineering Measurements
    - Verified by test
- IRD Requirements Verification Performed at UTD
  - Flowdown analysis complete by CDR
  - Engineering measurement test/verification during End Item Tests at UTD

---

**Complete Verification Matrix Contained in IRD**

---

- ICD Requirements Verification

- Physical – Analysis, Inspection
- Alignment – Test
- Structural - Test
- Electrical – Test
- Signal – Test
- Thermal – Analysis, Test
- EMI/EMC – Test
- Magnetic Induction – Test

THESE TESTS ARE  
PERFORMED DURING  
INSTRUMENT  
ENVIRONMENTAL TESTING,  
INTEGRATION TESTING  
WITH THE PAYLOAD  
MODULE, AND  
INTEGRATION TESTING  
WITH THE SPACECRAFT

**Complete Verification Matrix Contained in ICD**



- 
- a.       **Analysis** - This approach is used to verify compliance to requirements, which are not readily verified by other means. Examples include payload pointing accuracy, and reliability. Tools of this verification method include math models, simulations, compilation, and extension of test results.
  - b.       **Demonstration**- This approach is used to illustrate an end-item compliance to requirements by direct observation of the end-item operation. (Example: 1553B bus operation).
  - c.       **Inspection**- This verification approach is used to verify compliance to requirements through examination of the physical characteristics, visual properties, design schematics, etc., without the use of special laboratory tools, procedures, or services. Common examples are identification, size, weight, dimensions, cleanliness and documented records.
  - d.       **Test**- This verification approach is used to verify compliance to requirements through functional measurements, such as voltage levels and pulse width characteristics. This common verification method generally requires special laboratory equipment, detailed procedures, manual or automated data recording, etc.

---

# PERFORMANCE ASSURANCE

---

R.A. Heelis, WBH-CSS Director

- Center "CEO" has ultimate responsibility for ISO 9001 implementation

L.L. Harmon, WBH-CSS Quality Management System Representative

- Reports directly to Director
- Responsible for WBH-CSS quality system oversight (delegated from Director)
- Internal/external audits
- Responsible for WBH-CSS safety plan oversight
- ISO training

L.D. McCullough, SwRI Product Assurance Manager/Specialist

- Under contract to WBH-CSS to generate ISO 9001-2000 consistent documentation for the Center

---

C.R. Lippincott, WBH-CSS Program Manager

- Oversees project performance assurance programs

R.E. Garcia, CINDI Product Assurance Manager

- Responsible for implementation of CINDI Performance Assurance Implementation Plan
- Responsible for implementation of WBH-CSS and Project Safety Plan
- Conducts project quality system audits
- Reviews project procurement quality requirements/documents
- Monitors product assurance documentation
  - Procedures
  - Travelers
  - Test reports
- Conducts training


- 
- Extensive NASA/DoD experience
  - PA plan based on past experience
    - Basic plan previously approved by NASA and DoD projects
      - AE, DE, San Marco, DMSP
    - Tailored for SMEX SRQA requirements
      - Appendix added to basic plan
  - PA personnel participate in all program phases including procurement
  - Consistent with ISO 9001
    - Contains key ISO 9001 elements

- 
- Appendix added to base plan to cover SMEX SRQA requirements
  - SMEX appendix overview
    - PI Responsibility
    - Continuous Risk Management
    - Subcontractors and Suppliers
    - Parts and Workmanship Quality
    - System Safety
    - Consistent with ISO 9001
    - Workmanship Standards
    - Assurance Audits and Reporting
    - Failure Reporting
    - Reviews
      - Peer Reviews
      - Semiformal/Formal Reviews
      - Red Team
    - Systems Safety Implementation Plan
    - Safety Data Package
  - EEE Parts Program
    - Parts Lists
    - GIDEP Reports
  - Materials and Processes Control
    - Materials Lists
  - Probabilistic Risk Assessment
  - Contamination Control
  - Software
  - Verification
  - Mission Ops/Reports

- 
- UTD Base Plan used on previous successful NASA and DOD programs
  - Base Plan Overview
    - Management
    - Procurement Requirements
    - Audits/Reviews
    - EEE Parts Control
      - Selection/PCB
      - Nonstandard Parts Approval
      - Application
      - Radiation Tolerance
      - Parts List
      - Traceability
      - Procurement Controls
      - GIDEP Reporting and Follow-up
    - Materials and Processes Control
      - Materials Lists
      - MRB
    - Drawing/Specification Control
    - Identification and Traceability
  - Analyses
    - Electrical Derating/Stress
    - Radiation Tolerance
    - Reliability Prediction
    - Thermal
    - Structural
  - Configuration Management
    - Approval by AFRL/NASA of Interface/Performance Changes from the MRD, ICD or CDR
  - Document Change Control
  - Procurement Requirements Control
  - Nonconformance Control
  - Malfunction Reporting to AFRL/NASA
  - Fabrication/Workmanship Control
  - Inspections and Tests
  - Calibration of Test Equipment
    - Traceable to NBS
  - Training/Certification of Personnel
-

- 
- Plan satisfies NASA requirements and AFRL requirements with the following additions
    - Preliminary and final parts lists and materials lists
    - Hazards list
    - Safety contributions to mission safety document
    - Instrument environmental testing
    - MIL-STD-1540 temperature cycling requirements
    - Functional configuration audit






- 
- No major sub-contractors
  - Quality requirements imposed on suppliers
    - Quality/reliability requirements on purchase documents
    - Source Control Drawings for unique components
  - Audits of outside vendor capabilities and quality control
    - Machine shops
    - Plating facilities
    - Test facilities
  - 100% in-house inspection of outside fabrication/plating
  - Receiving inspection/traceability for all flight parts

- 
- Drawings signed off - placed under control
  - Latest issue of master drawings on central server
  - Master drawings are read only on server
  - Changes by engineering change order only
  - Planning sheets (travelers) generated for fabrication & inspection
    - Each step signed by performer
  - Single controlled drawing (shop copy) utilized for fab
  - Planning sheet/controlled drawings document "as built" condition
  - Documentation kept in controlled file

- 
- 100% in-house design
  - Drawing review and sign-off by responsible personnel including QA
  - Planning sheets (travelers) and drawings released for fabrication by cognizant engineers and QA
  - Blank boards and mechanical parts (including plating) fabricated by qualified outside vendors
  - 100% in-house inspection
  - Batch numbers (traceability) assigned to all purchased and fabricated parts/subassys
  - Boards and parts cleaned and stored in controlled storage until needed for assembly

- 
- 100% in-house electrical and mechanical assembly and inspection
  - Planning sheets utilized for control and record keeping (part/subassy batch numbers recorded)
  - Controlled access assembly and test areas
  - Trained/certified assemblers and inspectors
  - Laminar flow benches utilized
  - All workstations and equipment grounded
  - ESD training and wrist straps utilized
  - Special tools and test equipment calibrated
  - In-house bench, vacuum and temperature testing
  - Formal test procedures utilized/test data recorded
  - In-process and final inspections
  - Instrument environmental testing (vib., shock, TV, EMI, mag., etc.) accomplished at outside vendors
    - Environmental test procedures written by UTD and test vendor

## TYPICAL WORK FLOW CHART



QA QA INSPECTION

- 
- CAD/CAM drafting and machine shop
  - PWA inspection and assembly areas
  - Controlled access assembly and test areas
  - Laminar flow benches
  - Oil free vacuum test chamber
  - Electronic test and checkout equipment
  - Custom designed ion/electron sources for sensor test
  - Computational facilities
    - Laboratory & office computers
    - Dedicated UNIX cluster
    - Local supercomputers

- 
- Moderate Sensitivity to NVR in selected areas
  - Particulate contamination is of secondary concern
  - Materials Selection and Vent Paths
  - Cleanliness Emphasized During All Phases
    - Assy/Test Areas
    - Assembled Clean
    - White Glove Handling
  - Oil-Free Vacuum Systems
  - Personnel Training
  - Project contamination control plan
  - Extensive past successful experience utilizing the following procedures



# UTD CONTAMINATION CONTROL PROCEDURES

---

- Materials selection/processes
  - NASA RP-1124 utilized: 1.0% TML, 0.1% CVCM
- Cleanliness emphasized during all phases
  - Critical sensor assemblies accomplished on laminar flow (HEPA filtered) benches
  - Other assembly/testing in controlled environment
  - "White glove" handling
  - Protective covers for sensor apertures
  - Backfill NWM sensors
  - Instrument protected when out of controlled environment
  - Selective cleaning operations
- Oil free vacuum systems for testing
  - Gold plated sensor aperture covers with venting through labyrinths
- Personnel Training
- Instruments kept under class 100,000 conditions
  - Assembly and test
  - Integration
  - Encapsulation and carry
- Instrument purging not required
- Red tags removed as late as possible
- Clean exposed gold plated surfaces after red tag removal (UTD personnel)

# GENERAL I&T AND SV RECOMMENDATIONS/REQUESTS

---

- All parties utilize NASA RP-1124 for materials selection
  - 1.0% TML, 0.1% CVC
- SV venting away from sensors
- "White glove" handling during all phases
- Class 100,000 integration and environmental test areas
  - > Class 100,000 - Protect in shipping container or bag
    - Bagging considerations
      - Tape lifting aeroglaze paint
      - Solvents attacking aeroglaze paint
- Oil-free, monitored vacuum systems
  - TQCM and cold finger monitors and pre-test certification
    - Empty chamber TQCM level < 300Hz/hour (for 3 hours) with chamber shroud at 100C using a 10MHz TQCM at -20C
    - No pump oil residue on cold finger
  - Gold plated covers over sensor apertures - labyrinth venting
- "Clean" launch vehicle faring
- "Clean" launch vehicle purge gas/air


- 
- MIL-STD metal plating and finishing
  - NASA RP-1124 utilized (1.0% TML, 0.1%CVCM)
  - In-house processes and procedures well defined (listed in RQA plan)
  - Non-magnetic materials
  - Stress corrosion considered in metals selection
  - Non-flammable or flame retardant non-metals
  - Preliminary parts and materials lists have been submitted
  - Processes controlled by written procedures

- 
- Utilized past program experience
  - NASA RP-1124 database used for outgassing info
  - GSFC materials branch characterized "new Kel-F" (PCTFE)
  - Preliminary materials list submitted
  - Final materials list by CDR
  - Have responded to C/NOFS hazardous materials list


- 
- All safety info will be provided to AFRL/SA as required
  - No heaters planned
  - Enclosed volumes vented/no pressurized compartments
  - No dangerous materials
  - Materials selected using NASA RP-1124 and NHB 8060.1 as guidelines
  - No explosive devices, non-explosive initiators or radioactive materials
  - Connector mismatch prevention achieved by keying/markings
  - Handling fixtures not required
  - Shipping cases designed to protect instruments from mechanical damage and contamination
  - Instruments to remain in shipping cases when not on SV or in test
  - Observe standard ESD precautions
  - Connector savers utilized to prevent connector wear/damage
  - Personnel training

---

# **INSTRUMENT OVERVIEW**

ION VELOCITY METER  
OUTLINE/INTERFACE

# DRIFT METER PRINCIPLES OF OPERATION



**Supersonic Ions Form Beam behind Square Aperture**

**Split Collector Produces Collected Current Asymmetry**


**Ratio of Currents (Logarithm of Current Difference) proportional to  $\tan(\alpha)$**



# RETARDING POTENTIAL ANALYZER PRINCIPLES OF OPERATION

---


**Suppressor to Suppress  
electrons and photoelectrons**




**Retarding Grid Determines Kinetic Energy of Ions Having Access to the Collector**

**Collected Ion Current at a Given Retarding Potential is Dependent on  
Ion Mass ; Bulk Flow Velocity ; Temperature ; Aperture Plane Potential**


**Given the Mass Least Squares of Current vs Retarding Potential provides  
Bulk Flow Velocity ; Temperature ; Aperture Plane Potential**






- 
- NWM measures three orthogonal components of the neutral gas velocity.
  - These neutral wind components are coupled to the ion drifts and currents that trigger ESF irregularity growth.
  - Ram sensor measures changes in ram kinetic energy, where  $KE = \frac{1}{2}m(V_S + V_{RAM})^2$
  - Cross-track sensor measures differential pressure between chambers, where  $P_G = P_0[e^{-\pi^2 s^2} + \pi^2 s(1 + \text{erf}(s))](T_G/T_0)^{1/2}$
  - Chamber apertures are located on a dome such that pressure ratio in adjacent chambers is proportional to neutral arrival angle
  - One vertical aperture pair, one horizontal pair
-

# NWM RWS X-SECTION




RAM WIND SENSOR I-V  
CHARACTERISTIC

Effects of neutral gas temperature and ram velocity on collected ion current characteristic.

$$KE = \frac{1}{2}m(V_s + V_0)^2$$

# NWM FUNCTIONAL DIAGRAM SHEET 1


NWM FUNCTIONAL DIAGRAM  
Sheet 1



# NWM FUNCTIONAL DIAGRAM SHEET 2

NWM FUNCTIONAL DIAGRAM  
SHEET 2

7-6-01






---

# INTEGRATION AND TEST

- 
- Individual PWB assembly tests over temperature
  - Instrument test/calibration over temperature
    - Tests are designed to satisfy IRD verification matrix test requirements
  - Functional tests in vacuum, ambient temperature, sensor stimulation with ion source/gas jet
  - 200 hours minimum burn-in planned
  - Instrument Environmental Testing
    - Tests are designed to satisfy ICD verification matrix environmental test requirements
  - Integration with Payload Module at KAFB
  - Payload Module integration with S/V at SA
    - Standard functional tests defined for payload module/SV testing
-

# ASSEMBLY/INTEGRATION FLOW AT UTD

## INSTRUMENT ASSEMBLY/INTEGRATION FLOW



INSTRUMENT ENVIRONMENTAL TEST  
FACILITIES

---

TEST	TEST FACILITY
• Thermal cycling	• UTD
• Vibration/shock	• SwRI
• Thermal Vacuum	• SwRI
• EMI/EMC	• SwRI
• Magnetics	• GSFC

Quotes obtained from the above test facilities indicate that the services/facilities should be available on the estimated dates required

---

# **S/C INTEGRATION SUPPORT**

- 
- **Instrument to Payload Module integration/testing at KAFB**
    - **UTD personnel present for initial integration, full functional test, stimulation/sensor grid test**
    - **Routine test data initially evaluated by AFRL personnel, then FTP to UTD for detailed evaluation**
  - **Payload Module integration with S/C at Spectrum Astro**
    - **UTD personnel present for initial integration, full functional test, stimulation/sensor grid test**
    - **UTD personnel present for EMI/EMC, post-vib, TV, and final functional**
    - **UTD personnel perform sensor pump-out/backfill**
  - **Launch site support**
    - **UTD personnel present for FRR, final functional, and red tag item removal**
    - **Routine data evaluation via FTP**
  - **Early Orbit Checkout**
    - **UTD Personnel on-site at KAFB to participate in early orbit test plan execution**
-

---

# FLIGHT OPERATIONS

---

**Operations Overview**

**Optimized Workhorse Mode for IVM and NWS**

**IVM on all the time.**

**Slow offsets at selected local time/longitudes for Spread-F.**

**NWM on at altitudes below ~500 km**

**PE valve offset operation prior to perigee passes.**

**Operating Modes**

**a) Survey Mode**

**IVM Normal Mode.**

**IVM Slow Mode for some Spread-F studies**

**NWM Normal Mode Optimized for continuous operation through perigee.**

**b) Forecast Mode**

**IVM Normal Mode.**

**NWM Normal Mode Optimized for continuous operation through perigee.**

**c) Payload Burst Mode**

**No Special Operations**



---

**Special Operating Modes**

**a) Early Orbit Checkout**

**IVM Drift Meter Repeller Voltage for removal of H<sup>+</sup> signal  
IVM RPA retarding voltage sequence for ion composition  
NWM RWS and CTS emission current for acceptable signal  
NWM RWS ion source energy for acceptable signal  
NWM RWS retarding voltage sequence for optimal signal  
NWM CTS PE valve timing sequence for optimal signal.**

**Outgas NWM before HV/filament actuated**

**b) Campaigns**

**IVM RPA sweep rate and IDM offset rate can be maximized for specific objectives.**

**c) Backup modes and Anomaly Resolution**

**No redundant capabilities**

---

**On Orbit Calibrations**

**a) Internal Calibrations**

**IVM Drift Meter**

**Automatic Offset Sequence to remove electrometer offsets**

**NWM CTS**

**Pressure Equalization valve to remove gauge offsets**

**b) Satellite Calibrations**

**Slow s/c spin allows angular sensitivity of IDM, CTS and RWS to be determined**

**c) Cross-Calibration with other instruments**

**$E = -V \times B$  allows comparison with VEFI**

**IDM Ion Arrival Angles compare with DIDM**

**RPA total ion concentration compares with PLP**

---

## Day in the Life Operations

### **a) NWM**

**Low Voltage instrument elements on at all times.**


**High voltage multiplier and filaments turned-on below ~500 km**

**PE valve operation at fixed time after filament turn-on.**

### **b) IVM**

**Normal Operations Mode on at all times**

**No daily command sequences required.**



**Automatic Calendar and Notification  
for Data Transfer.**

**Data Reduction Codes Mirrored  
at each Site**

- 
- Predicted and Present Satellite Location updated every 20 minutes.
    - Available from web page.
  - Data Available 24 hours after access in space.
  - Quick-Look Plots produced from IDM only
    - Ni, Local Vertical & Local Cross-Track Ion Drift
  - Geophysical Data Records Produced and Accessible within 10 days
    - Level 2 Automatic Algorithms
      - Time Series Plots
      - ASCII Flat Files

---

# DATA ANALYSIS

---

## Major Responsibilities

### Algorithm Design

IVM

Heelis & Earle

NWM

Earle & Heelis

### Algorithm Execution

Power & Coley

### Instrument Behavior

IVM

Heelis & Earle

NWM

Mahaffy & Earle

### Data Quality

IVM

Heelis & Earle

NWM

Earle & Heelis

---

## 1. Raw Data

### **Neutral Wind Meter**

- a) 16 bit sample -- RWS log electrometer; PE valve open/closed; sync.
- b) 16 bit sample -- CTS vert diff amp ; PE valve open/closed; polarity ; sync.
- c) 16 bit sample -- CTS horiz diff amp ; PE valve open/closed; polarity ; sync.
- d) 16 bit sample -- CTS gauge electrometer ; PE valve open/closed; sync.

### **Ion Velocity Meter**

- a) 16 bit sample -- RPA lin electrometer; range ; sync.
- b) 16 bit sample -- IDM diff amp ; axis ; polarity ; sync.
- c) 16 bit sample -- IDM log electrometer ; sync.

## 2. Engineering Unit Conversion

### **Neutral Wind Meter**

- a) RWS log electrometer      -> Equivalent Current and Retarding Potential
- b) CTS vert diff amp          -> Vertical Neutral Arrival Angle
- c) CTS horiz diff amp        -> Horizontal Neutral Arrival Angle
- d) CTS gauge electrometer    -> Relative Neutral Pressure..

### **Ion Velocity Meter**

- a) RPA lin electrometer; range    -> Equivalent Current and Retarding Potential
- b) IDM diff amp ; axis ; polarity -> Horizontal and Vertical Ion Arrival Angle
- c) IDM log electrometer ; sync.   -> Relative Ion Density



### 3. Derived Data

#### **Neutral Wind Meter**

- |   |  |
|---|--|
| a) Equivalent Current and Retarding Potential | -> Neutral Drift Ram Component wrt s/c           |
| b) Vertical Neutral Arrival Angle             | -> Neutral Drift Vertical Component wrt s/c      |
| c) Horizontal Neutral Arrival Angle           | -> Neutral Drift Horizontal<br>Component wrt s/c |
| d) Relative Neutral Pressure                  | -> Relative Ambient Pressure Estimate            |

#### **Ion Velocity Meter**

- |   |   |
|---|---|
| a) Equivalent Current and Retarding Potential | -> Ion Drift Ram Component wrt s/c ;<br>Ion Comp. and Temp. |
| b) Horizontal and Vertical Ion Arrival Angle  | -> Ion Drift Vertical and Horizontal<br>Components wrt s/c  |
| c) Relative Ion Density                       | -> Ambient Total Ion Concentration                          |

---

#### 4. Algorithm Design

**Neutral Wind Meter** - FORTRAN code also delivered to C/NOFS Data Center

- a) Least Squares Fitting Procedure for Neutral Drift Ram Component wrt s/c
- b) Removal of Difference Amplifier Offsets for Neutral Arrival Angles wrt s/c
- c) Removal of Spacecraft Velocity Vector for Ambient drifts wrt to s/c
- d) Rotation of s/c reference axes to Earth Fixed Coordinates.

**Ion Velocity Meter** - FORTRAN code also delivered to C/NOFS Data Center

- a) Least Squares Fitting Procedure for Ion Drift Ram Component wrt s/c  
Ion Temp and Composition
- b) Removal of Difference Amplifier Offsets for Ion Arrival Angles wrt s/c
- c) Removal of Spacecraft Velocity Vector for Ambient drifts wrt to s/c
- d) Rotation of s/c reference axes to Earth Fixed Coordinates.

---

## **5. Data Products**

### **Neutral Wind Meter** - Digital data file in CINDI Data Archive

- a) Neutral Wind Vector in s/c coordinates and Earth Fixed Coordinates.
- b) Cross Track wind components in s/c coordinates.
- c) Measurement location in UT and Earth Fixed Coordinates

### **Ion Velocity Meter** - Digital data file in CINDI Data Archive

- a) Ion Drift Vector in s/c coordinates and Earth Fixed Coordinates.
- b) Total Ion Concentration, Ion Temperature, Ion Composition
- c) Cross Track ion drift components in s/c coordinates.
- d) Measurement location in UT and Earth Fixed Coordinates

## **6. Required Spacecraft and Operations Data**

- a) CINDI instrument data packets**  
**UT stamped**
- b) Spacecraft Reference Axes.**  
**Pitch, Roll and Yaw defined wrt spacecraft velocity vector**
- c) Spacecraft Location in Earth Fixed frame.**  
**UT, Geographic Latitude, Geographic Longitude,**  
**Radial Distance from Earth center.**
- d) Direction cosines of s/c velocity vector in Earth Fixed frame.**  
**UT stamped**
- e) Interpolated data required to provide 1/4 second temporal resolution.**

---

# PROJECT MANAGEMENT - COST

- 
- System engineering process based on defining the measurements required to meet scientific objectives
  - Developed for WBS on Excel spreadsheets
  - Include SOW requirements, match to schedule and develop in WBS
  - Bottom-up estimating process
  - Derived from past performance
  - Compare to other similar instruments and projects of similar complexity
  - Quotations on major outside elements
  - PI, PM, SE, Mechanical/Thermal Engineer, and Computer System/Software Engineer are primary estimators

- 
- Costs reconciled, tracked, and reported monthly out of PM office
  - Costs accrued in WBS
  - WBS linked to cost reporting system
  - Reported on NASA Forms 533M and 533Q
    - Actual costs and future estimates
    - Estimated cost to completion
  - Use cost to milestone metric
    - Spending rate and acc. total for salaries and wages per phase per WBS
    - Spending rate and acc. total for significant other items, e.g. parts, subcontracts, purchased services
  - Identify and evaluate any projections to completion that exceed budget
  - Apply solutions to fit case
    - Monitor
    - Adjust control variables
    - Descope
  - Early identification and reaction
-

- 
- Operating on Pre-award provision of Phase B/C/D/E
    - \$210k through 31 Aug 01, can be extended a week
  - Additional funding of \$619k through 15 Nov 01 with Phase B/C/D/E contract signed
  - GSFC Co-Investigator funded directly
  - \$400k S/C IVM Integration Charges paid by NASA



## SUMMARY RY COSTS

---

ITEM	FY2001	FY2002	FY2003	FY2004	FY2005	FY2006	FY2007	Total RY \$K
<b>Phase A</b>								
UTD	220							220
GSFC	30							30
<b>Bridge Phase</b>								
UTD	229							229
GSFC	21							21
<b>Phase C/D</b>								
UTD	442	2653	2424	995				6514
GSFC	22	128	158					308
Air Force	400							400
<b>Phase E</b>								
UTD				919	1070	555	64	2608
GSFC				140	100	66		306
<b>NASA OSS Mission Cost</b>	1,364	2,781	2,582	2,054	1,170	621	64	10,636

## CURRENT COST ESTIMATE 1

Cost Element	FY2001	FY2002	FY2003	FY2004	FY2005	FY2006	FY2007	Total RY \$K
Phase A								
UTD	220							220
P.Mahaffy (GSFC)	30							30
Reserves								
<b>Total Phase A</b>	250							250
Bridge Phase								
UTD	229							229
P.Mahaffy (GSFC)	21							21
Reserves								
<b>Total Bridge Phase</b>	250							250
Phase C/D								
NWM Instrument	247	1330	429	0	0	0	0	2005
NWM S/C Int & Test	0	0	695	122	0	0	0	817
NWM Pre-Launch Data SW	15	90	153	25	0	0	0	283
IVM Instrument	166	944	202	0	0	0	0	1311
IVM S/C Int & Test	0	39	499	76	0	0	0	614
IVM Pre-Launch Data SW	10	55	107	17	0	0	0	189
E/PO- C/D	0	20	62	10				92
Science Team - C/D	4	26	27	5				63
P.Mahaffy (GSFC)	22	128	158					308
Air Force S/C Int Charges - IVM	400							400
<i>Subtotal C/D before Reserves</i>	864	2631	2332	256	0	0	0	6083
Reserves		150	250	739				1139
<b>Total Phase C/D</b>	864	2781	2582	995	0	0	0	7222
Phase E								
NWM Database Management	0	0	0	327	267	125	15	734
NWM Science Analysis	0	0	0	148	272	157	18	595
IVM Database Management	0	0	0	218	178	85	10	490
IVM Science Analysis	0	0	0	148	273	158	18	597
E/PO- E				52	49	0	0	101
Science Team - E				27	31	30	3	91
P.Mahaffy (GSFC)				140	100	66		306
<i>Subtotal Phase E before Reserves</i>	0	0	0	1059	1170	621	64	2914
Reserves								0
<b>Total Phase E</b>	0	0	0	1059	1170	621	64	2914
<b>Total NASA Cost</b>	1364	2781	2582	2054	1170	621	64	10636

- 
- Total Cost estimate unchanged from Phase A Study
  - Better definition in some areas, details rearranged
    - Higher parts quality in some areas
    - Back-up parts for quality and schedule mitigation
    - Increase NIAT estimate
    - Above taken from old margin
  - Current margin
    - No reserve on
      - Phase A
      - Bridge Phase
      - \$400k Air Force cost
      - Phase E
        - Level of effort
        - Intellectual Pursuit of Science Adjusts

Base per above boundary conditions = \$5,683k

Reserves = \$1,139k

Margin = 20%